

Quarterly Communications Meeting on the Long-Term Plan for Achieving Water Quality Goals for the Everglades Protection Area Tributary Basins

A-1 Flow Equalization Basin (FEB)

August 23, 2013

*John Mitnik, P.E.
Bureau Chief
Engineering and Construction*

PROJECT LOCATION



FLOW EQUILILIZATION BASIN DESIGN



- Features
 - 15,000 acres
 - 4 feet in depth
 - 60,000 acre-ft temporary storage
 - Utilize internal east – west Agricultural Canals as spreader canals
 - Uniform north-south flow
- Inflows
 - Canal Inflows
 - NNRC Canal (S-2 & S-7 Water Basin)
 - Miami Canal (S-8 Water Basin)
- Outflows
 - Evapotranspiration
 - Seepage
 - STA Releases




EXISTING SITE CONDITIONS




- STA-3/4 Supply / Inflow Canal
- East - West Agricultural Roads, Canals and Levees
- North - South Agricultural Canals / Berms and Typical East - West Swales
- Sorted Stockpiles
- Test Cells
- Perimeter Scraped Area

DEMOLITION




- Typical Perimeter Stockpile Demolition
 - Existing Seepage Canal
 - Excavation Spoils Piles
 - Existing Scraped Area
- Typical Major Haul Road Demolition
 - Existing East - West Roads and Canals
 - Existing North - South Haul Roads
 - Existing Perimeter Haul Road
- Typical North - South Road / Berm Demolition
- Typical East - West Swale
- Typical Perimeter Muck Berm and Dewatering Cells Demolition
 - Existing Perimeter Muck Berms
 - Existing Dewatering Cell Muck Berms
 - Existing Scraped Area

DEMOLITION (con't)



TALSIMAN AGRICULTURAL PUMP STATION
'LOOKING EAST'




TEST CELL



CABASSA AGRICULTURAL PUMP STATION
'LOOKING WEST'




CIVIL DESIGN





EAA A-1 FEB (INFLOW OPERATIONS)



- Inflow from G-372
 - G-720 Open
 - 2,775 cfs to FEB
 - 925 cfs to STA-3/4
Inflow Canal
 - Inflow Canal Design Stage
 - +13.6' NAVD 88



G-720




G-721

- Inflow from G-370
 - G-721 Open
 - 1,850 cfs to FEB
 - 925 cfs to STA-3/4
Inflow Canal
 - Inflow Canal Design Stage
 - +13.6' NAVD 88

EAA A-1 FEB (OUTFLOW OPERATIONS)



- Outflow Structures G-722W and G-722 in southeastern corner of site
 - Water from FEB transported east, through G-722W, and discharged to NNRC.
 - $Q_{\max} = 2,000$ cfs
- Outflow Structures G-724 (A-J) along south perimeter levee
 - **Gravity flow discharge**
 - Available during times that the FEB WSE is above the operating stage of the STA-3/4 Inflow canal.
 - $Q_{\max} = 2,000$ cfs at 3 foot head differential.



WATER CONTROL STRUCTURE – G-720




- **Location:** Along west levee of EAA A-1 FEB; 7.4 Miles east of G-372
- **Purpose:** Divert flows from STA-3/4 Supply Canal into the FEB West inflow canal
- **3 - Bay Reinforced Concrete Gated Spillway**
 - 11.25 feet tall by 20 feet wide per bay
 - Vertical lift roller gates




Typical 3 Bay Gated Spillway

- **Type Hoist:** Electric Motor drum and Cable hoist; or portable power-drive for manual operations
- **Control by remote telemetry through SFWMD SCADA system**
- **Normal Power Source:** Commercial Electricity
- **Emergency Power Source:** Portable Backup generator



G-720 Design Layout

WATER CONTROL STRUCTURE - G-720



G-720 3-D Model Looking North

WATER CONTROL STRUCTURE - G-721




- **Location:** Along southeastern perimeter levee of EAA A-1 FEB; northwest of G-370
- **Purpose:** Divert flows from STA-3/4 Inflow Canal into the FEB East inflow canal
- **2 - Bay Reinforced Concrete Gate Spillway**
 - 9.75 feet tall by 20 feet wide per bay
 - Vertical lift roller gate




Typical 2 Bay Gated Spillway

- **Type Hoist:** Electric Motor drum and Cable hoist; or portable power-drive for manual operations
- **Control** by remote telemetry through SFWMD SCADA system
- **Normal Power Source:** Commercial Electricity
- **Emergency Power Source:** Emergency power supplied from G-370



G-721 Design Layout

WATER CONTROL STRUCTURE - G-721




G-721 3-D Model Looking North

WATER CONTROL STRUCTURE - G-722W




- Location: Underneath G-721 Inflow canal; Southeastern corner FEB Collection and Conveyance Canal west of G-722
- Purpose: Deliver water from interior of FEB to G-722 outflow canal
- 3 - Barrel Reinforced Concrete Box Culvert
 - 10 feet tall; 10 feet wide; 606 feet length
 - Non-gated culvert structure




Above: G-722W Plan view Looking North

Below: G-722W Profile



WATER CONTROL STRUCTURE – G-722W



G-722W 3-D Model Looking Northwest


WATER CONTROL STRUCTURE – G-722



- **Location:** Underneath access roadway serving G-370; Southeastern corner FEB Collection and Conveyance Canal
- **Purpose:** Deliver flows from FEB interior to the headwater side of G-370
- **3 - Barrel Reinforced Concrete Gate Culvert**
 - 10 feet tall; 10 feet wide; 31 feet length
 - Stem operated vertical lift slide gates




Typical Stem Operated Slide Gate



G-722 Design Layout

- **Type Hoist:** Pedestal mounted, single stem hoist with electric motor; Hand wheel for manual operations
- **Control** by remote telemetry through SFWMD SCADA system
- **Normal Power Source:** Commercial Electricity
- **Emergency Power Source:** Manual or emergency power from G-370

WATER CONTROL STRUCTURE - G-722



G-722 3-D Model Looking Southeast


WATER CONTROL STRUCTURE - 724 (A-J)



- Location: Along south perimeter
- Purpose: Deliver flows from EAA A-1 FEB to STA-3/4 Inflow Canal; Function as outflow structures directly to STA-3/4 Inflow Canal by gravity flow.
- 1 - Barrel Reinforced Concrete Gate Culvert
 - 7.5 feet tall; 7.5 feet wide; 23 feet length



Typical Stem Operated Slide Gate



G-724 Typical Design Layout

- Type Hoist: Pedestal mounted, screw type hoist with electric motor; Hand wheel for manual operations
- Control by remote telemetry through SFWMD SCADA system
- Normal Power Source: Solar Electricity
- Emergency Power Source: Manual or temporary portable generator

A-1 FEB

- Design and Construction Schedule:

- Preliminary Design Completed
- Intermediate Design Submittal Completed
- Final Design Submittal Completed
- Final Design TRB Completed
- Corrected Final/RTA Design Submittal Completed
- Governing Board October 2013
- NTP November 1, 2013
- Substantial Completion December 31, 2014
- Final Completion March 31, 2015

Milestones

Milestone	Compliance date	Status
Initiate design	4/1/2012	Complete
Submit state and federal permits	12/1/2012	Complete
Design status report	3/1/2013	Complete
Complete design	8/1/2013	Complete
Initiate construction	6/30/2014	Pending
Construction status report	3/1/2015	Pending
Construction status report	3/1/2016	Pending
Completion of construction	7/30/2016	Pending
Initial flooding and optimization complete	7/29/2018	Pending

QUESTIONS...



EAA A-1 FEB looking east from southwest corner