The STA-3/4 Periphyton Stormwater Treatment Facility

Presented April 20, 2010

by: Michael Chimney South Florida Water Management District

STA-3/4 PSTA Implementation Project

- PSTA = Periphyton-based Stormwater Treatment Area
- Periphyton = algal community attached to surfaces
- SAV = Submersed aquatic vegetation
- Project constructed in western portion of STA-3/4 Cell 2B
- Encompasses 400 acres (162 ha)
 - Upper SAV Cell = 200 acres (81 ha)
 - Adjacent Lower SAV and PSTA Cell = each 100 acres (40 ha)
- Removed soil down to caprock in the PSTA Cell, floor elevation ~ 2 feet lower in PSTA Cell => reduce P flux from old agricultural soil



STA-3/4 PSTA Implementation Project

- Project planning initiated June 2003
- Design completed December 2003
- Construction started March 2004
- Infrastructure construction substantially complete -July 2005
- Outflow from PSTA Cell initiated June 2006
- Cost ~ \$3.5M (capital items) + additional ongoing operating & monitoring costs



District PSTA Platforms (1997 – 2010)

Raceways (troughs @ 9 cm D x 1 ft W x 100 ft L)



Mesocosms (tanks @ 10 – 60 cm D x 1 m W x 6 m L)





District PSTA Platforms (cont.)

> ENRP Test Cells (each @ 0.5 ac)



Field-scale Cells (each @ 5 ac)





District PSTA Platforms (cont.)


> STA-3/4 PSTA Cell (100 ac – a full scale project)






Stormwater Treatment Areas 101

- > Physical, chemical and biological P removal processes
- Outflow TP equilibrium between P removal processes & sediment P flux back to water column



Location of STA-3/4 PSTA Implementation Project






PSTA Cell Water Control Structures

- Peat removed down to caprock
- > Avg. depth ~ 2 ft
- Target HRT ~ 5 day

Outflow Pumps (G-388)








Outflow Pump Station Operation

- Needed to maintain shallow depth in PSTA Cell
- > Two 100 cfs electric pumps (42 inch diameter)
- Pumps operated in automatic mode, triggered by a float switch that tracks stage in PSTA Cell
- Pumps turn on at stage = 10.25 ft NGVD and off when stage = 9.75 ft NGVD, water depth oscillates
- Average cell depth ~ 2 feet
- Nominal hydraulic retention time in PSTA Cell: ~ 5 days
 - Controlled by adjusting inflow gate openings



Outflow Pump Station Headwater Stage






Veg strips in lower SAV and PSTA Cells





Surface Inflow/Outflow POR TP



Next Steps

- Analyze relevant water quality, hydraulic and operations data from all PSTA platforms
- Develop a consolidated report summarizing the current scientific understanding of PSTA and implementation options
- Pursue engineering and construction feasibility of large-scale implementation options

