



# Periphyton Stormwater Treatment Area (PSTA) Studies - STA-1E

Palm Beach County, FL  
June 30, 2009

Dr. Ronald D. Jones  
Portland State University  
Email: [jonesrd1@verizon.net](mailto:jonesrd1@verizon.net)  
Phone: (971) 322-8078



**10 ppb  
TP**



The background of the slide is a composite image. The top left shows an aerial view of a large dam with water flowing through its spillways. The bottom right shows a close-up view of a wastewater treatment facility with several rectangular concrete basins containing water and green reeds. The entire background is overlaid with a dark blue gradient.

# Agenda

- Introduction and Overview
- Mesocosm Results
- Field Scale Demonstration
- Path Forward

# STA-1E

## PSTA Demonstration Conceptual Plan to Achieve 10 ppb Phosphorus




Emergent  
Growth



SAV  
w/Periphyton



Calcareous  
Periphyton  
(activated)




low phosphorus substrate


# Natural System

Seasonal Dryout

**CYANO  
DOMINANT**  
Dry conditions  
Summer/Fall




**DIATOM  
DOMINANT**  
Wet conditions  
Winter/Spring



# Corps PSTA

Repeated (forced) Dryouts  
Activated Periphyton






**CYANO DOMINANT**  
Extreme conditions

# Mesocosm Study

**PSTA**

Water Hyacinth



- Substrate types
- Hydraulic retention times
- Flow depths
- Vegetative community size and sustainability

# Mesocosm Water Budget




rainfall and  
evaporation  
monitoring



composite  
sampling  
(2000 hrs; 1400 hrs)

# Mesocosm : Results (7/2007 through 6/2008)



Cell 1 = lime sludge (over riviera sand)

Cell 2 = limestone - Ft. Thompson (~7 years)

Cell 3 = limestone - Onsite (~2 year)


Cell 4 = limestone - Ft. Thompson over peat (~7 years)

# Field Scale Demonstration

- In 2003 PSTA Field-Scale Demonstration was authorized and funded
- PSTA Field Scale Demonstration Objectives:
  - Evaluate PSTA performance for the period of record in a larger scale
  - Calibrate concentration-based PSTA model to determine full scale sizing of PSTA technology
  - Demonstrate most cost-effective PSTA substrate
  - Determine PSTA engineering and operational parameters for full scale implementation
  - Determine the operations and maintenance requirements for full scale implementation and sustainability



# PSTA Field-Scale Test Cells



C-51

CELL 1

PLUG ●

SAV CELL

C

B

A

CELL 2 BYPASS

6" ONSITE  
LIMESTONE


6" ONSITE  
LIMESTONE

1" PALM BEACH  
LIME SLUDGE OVER  
NATIVE SAND

SEEPAGE CANAL

# PSTA Field Scale Demonstration Results


## 1" Lime Sludge - Cell A



Note: results based on a 3.5 - 7 day hydraulic retention time

# PSTA Field Scale Demonstration Results


## 6" Onsite Limestone - Cell B



Note: results based on a 3.5 - 7 day hydraulic retention time

# PSTA Field Scale Demonstration Results

## 6" Onsite Limestone - Cell C



Note: results based on a 3.5 - 7 day hydraulic retention time


# **PSTA Field Scale Demonstration**

## **Path Forward**

- Operate temporary (10cfs) pumps from C-51 during low flow periods to bypass cell 1
- Plug installed isolating test cells from cell 2 bypass area, to enable testing during high flow
- Current Schedule:
  - Testing completion - August 2010
  - Prepare Engineering Documentation Report (EDR) – January 2011


# Field –Scale Operation (STA 1-E)

November 2006 – July 2009



←→ Planned schedule alternating 2 months wet, 2 months dry for a period of 6-8 months

# PSTA Field-Scale Test Cells



C-51

CELL 1

PLUG ●

SAV CELL

C

B

A

CELL 2 BYPASS

6" ONSITE  
LIMESTONE

6" ONSITE  
LIMESTONE

1" PALM BEACH  
LIME SLUDGE OVER  
NATIVE SAND

SEEPAGE CANAL

# **BACK-UP SLIDES**



# Chemical & Biological Reactants Naturally Found in the Everglades Marsh

- Calcium - abundant
- Magnesium - trace
- Iron - trace
- Aluminum - trace
- Manganese – trace

Require  
Chemical  
Treatment

Calcium-based treatment technology only logical option


# Hypothesis – Factors for Developing Calcareous Periphyton

- High solar radiation
- High temperature
- Low phosphorous
- Dry-out

**Manipulate hydroperiod – forced dry-outs**

# Corps Activated Periphyton:

Water Treatment Based on Observations in Nature  
(natural system enhanced through more frequent dry-outs)



## Post-Tamiami Trail Construction

- Low Phosphorus
- Rainfall Driven
- Periodic Dryouts (cyano bacteria dominance)
- Calcite (precipitated periphyton)

→ 1920s

## Pre-Tamiami Trail Construction


(no obstruction to sheetflow in Everglades)


- Low Phosphorus
- Always Wet

**Core Sample South  
of Tamiami Trail  
Natural Conditions**

# PSTA Phosphorus (P) Removal Process within a Calcareous Periphyton Mat

- Calcium ( $\text{Ca}^{2+}$ )
- Dissolved Inorganic Carbon – DIC (e.g.  $\text{CO}_3^{--}$ ,  $\text{H}_2\text{CO}_3$ ,  $\text{HCO}_3^-$ ,  $\text{CO}_2$ )
- High pH
- Nucleation Sites





**Enlargement of Calcareous Periphyton Assemblage**  
calcium carbonate precipitation functional groups