

Contents

VOLUME 1

Section	Page
ES	Executive Summary of Managed Wetlands Treatment System Testing..... ES-1
ES.1	Introduction..... ES-1
ES.2	Purpose ES-1
ES.3	Experimental Design and Methods ES-2
ES.4	Summary of Results ES-4
ES.4.1	Everglades Nutrient Removal Test Cell Experimental Results..... ES-4
ES.4.2	Chemical Treatment Pilot Plant Operation..... ES-9
ES.4.3	Paired Watershed Experimental Design Analysis ES-10
ES.4.4	Evaluation of Marsh Readiness ES-10
ES.5	Verification Tests ES-11
ES.6	Summary..... ES-12
1.0	Introduction.....1-1
1.1	Background1-1
1.2	Treatment Process1-1
1.3	Research Objectives.....1-2
1.4	Testing Philosophy.....1-4
1.5	Key Technical Issues1-5
1.5.1	Characterization of TP Removal Efficiency in an MWTS1-5
1.5.2	Determination of Chemical Treatment Variables1-5
1.5.3	Characterization of Nature and Efficiency of Ionic Conditioning in a Wetland.....1-6
1.5.4	Management and Fate of Solids.....1-6
1.6	MWTS Experimental Design1-6
1.7	MWTS Scientific Review Panel.....1-9
2.0	Methods, Materials, and Descriptions of Chemical Treatment Pilot Units.....2-1
2.1	Methods and Materials.....2-1
2.1.1	Laboratory Prescreening for Chemical Selection2-1
2.1.3	Field Sampling at ENR Test Cells.....2-4
2.1.4	Verification Testing Program.....2-6
2.1.5	Paired Watershed Analysis2-10
2.1.7	Tracer Study2-11
2.2	Description of Chemical Treatment Pilot Units2-12
2.2.1	Pilot Treatment Units at ENR Test Cells2-12
2.2.2	Description of the Cypress Demonstration Pilot.....2-17

Section	Page
3.0 Meteorological Data.....	3-1
3.1 Solar Radiation.....	3-1
3.2 Air Temperature.....	3-2
3.3 Rainfall	3-2
3.4 Evapotranspiration.....	3-2
4. Results of Testing and Evaluations at MWTS Test Cells and Seminole Reservation Wetland Site.....	4-1
4.1 MWTS North and South Test Cells.....	4-1
4.1.1 General Features	4-1
4.1.2 Operation of Chemical Treatment Units at ENR.....	4-1
4.2 Vegetation in Test Cells	4-8
4.3 Water Regime.....	4-8
4.3.1 Water Depth	4-8
4.3.2 Hydraulic Loading Rate	4-12
4.3.3 Water Balance.....	4-12
4.1.4 Tracer Study	4-16
4.3.4 Summary	4-19
4.4 Field Parameters	4-21
4.5 Water Quality Data	4-26
4.5.1 Chemical Treatment Units.....	4-26
4.5.2 General Water Quality Results	4-26
4.5.3 Phosphorous.....	4-36
4.1.4 Nitrogen	4-48
4.1.5 Other Water Quality Parameters.....	4-48
4.6 Mass Balances	4-50
4.6.1 Phosphorous.....	4-50
4.6.2 Nitrogen	4-72
4.7 Paired Watershed Analysis.....	4-73
4.7.1 Introduction.....	4-73
4.7.2 Methods	4-74
4.7.3 Statistical Analysis.....	4-74
4.7.4 Results	4-75
4.7.5 Soluble Reactive Phosphorous.....	4-82
4.7.6 Total Dissolved Phosphorous	4-88
4.7.7 Summary	4-88
4.8 Other Parameters.....	4-88
4.9 Toxicity Tests	4-117
4.9.1 Physical-Chemical Verification Testing.....	4-117
4.9.2 Toxicity Testing.....	4-117
4.9.3 AGP Testing.....	4-119
4.9.4 TCLP Analysis.....	4-119
4.9.5 Summary	4-119
4.10 Soils and Solids	4-122
4.11 Hydraulic Test of Phase 2 Wetland.....	4-130

Section	Page
5.0 Marsh Readiness and Ionic Conditioning.....	5-1
5.1 Methods	5-1
5.2 Results	5-2
5.2.1 Calibration Period.....	5-3
5.2.2 Treatment Period	5-4
5.3 Summary.....	5-7
6.0 Summary and Recommendations	6-1
6.1 Summary of MWTS Testing.....	6-1
6.1.1 Project Planning & Startup	6-1
6.1.2 Chemical Selection.....	6-2
6.1.3 Baseline Calibration Period	6-2
6.1.4 Treatment and Verification Periods	6-2

VOLUME 2

Appendices

A	Laboratory Prescreening for Chemical Selection
B	Testing Polyaluminum Chloride
C	Trace Study Data
D	Description of the Big Cypress Seminole Indian Reservation Demonstration Pilot
E	Water Regime Time Series Charts
F	Water Quality Time Series Charts
G	Water Quality Gradient Time Series Charts
H	Paired Watershed Regression Analysis
I	Toxicity Test Report
J	ENR Chemical Treatment Unit Design
K	North Test Cell Pilot Unit Evaluation
L	Operation Records for ENR Pilot Units

Exhibits	Page
ES-1 (A) Time series of TP inflow and outflows for NTCs over treatment period April through December 2000. (B) TP time series for final 4 months Of treatment period.....	ES-5
ES-2 (A) Time series of TP inflow and outflows for STCs over treatment period of April through December 2000 (B) TP time series for final 4 months of treatment period	ES-6
ES-3 Boxplot Summaries of TP Inflow and Outflows Over Final 4 Months of Testing for NTCs (top) and STCs (bottom).....	ES-7
1-1 Schematic of Managed Wetlands Treatment System	1-2
1-2 Experimental Treatments	1-7
2-1 Research Schedule	2-2
2-2 Sampling Parameters for the ENR MWTS.....	2-5
2-3 Plan View of Typical ENR Test Cell Showing Sampling Locations	2-7
2-4 Operational Sampling Plan for ENR MWTS	2-8
2-5 Summary of Background Lithium Concentrations at the MWTS Test Cells	2-12
2-6 Splitter Box For Alum Coagulant Systems	2-14
2-7 P & I Diagram for Alum Coagulant System Pilot Plant.....	2-16
2-8 Alum Equipment Arrangement	2-17
3-1 Total Solar Radiation Measured at the South ENR STRC	3-1
3-2 Photosynthetically Active Radiation Measured at the South ENR STRC.....	3-1
3-3 Average Daily Air Temperature Data at the South ENR STRC.....	3-3
3-4 Daily Rainfall Data at the ENR Rainfall Stations	3-4
3-5 Daily Evapotranspiration Data at the ENR Evapotranspiration Station.....	3-5
4-1 General Design Summary of the MWTS Test Cell.....	4-1
4-2 Chronology of MWTS Pilot Plant Operations at the ENR.....	4-2
4-3 Percent Cover of Dominant Vegetation in NTC Test Cells for Six Sampling Events Over the Project Period.....	4-9
4-4 Percent Cover of Dominant Vegetation in STC Test Cells for Four Sampling Events Over the Project Period.....	4-10
4-5 Water Regime Data at the North and South ENR Test Cells, July 1999 through December 2000.....	4-11
4-6 MWTS Water Quality Stations	4-13
4-7 Cumulative Monthly Inflow and Outflow from the North Test Cells (Calc. Outflow Method).....	4-14
4-8 Cumulative Monthly Inflow and Outflow from the North Test Cells (Weir Staff Method).....	4-17
4-9 Summary of Operating Conditions and Tracer Study Results	4-16
4-10 Normalized RTDs for the North Test Cells	4-20
4-11 Normalized RTDs for the South Test Cells.....	4-20
4-12 Monthly Averages of Field Measurements Collected from the MWTS Test Cells, July 1999 to December 2000	4-22

Exhibits	Page
4-13 Calibration and Treatment Period Average Values of Water Quality Data Collected at the MWTS Test Cells	4-27
4-14 Inflow and Outflow Weekly Average Values for Total Phosphorous, Total Dissolved Phosphorous, and Total Particulate Phosphorous for MWTS North Test Cell 2	4-30
4-15 Inflow and Outflow Weekly Average Values for Total Phosphorous, Total Dissolved Phosphorous, and Total Particulate Phosphorous for MWTS North Test Cell 3	4-31
4-16 Inflow and Outflow Weekly Average Values for Total Phosphorous, Total Dissolved Phosphorous, and Total Particulate Phosphorous for MWTS North Test Cell 4	4-32
4-17 Inflow and Outflow Weekly Average Values for Total Phosphorous, Total Dissolved Phosphorous and Total Particulate Phosphorous for MWTS South Test Cell 5	4-33
4-18 Inflow and Outflow Weekly Average Values for Total Phosphorous, Total Dissolved Phosphorous and Total Particulate Phosphorous for MWTS South Test Cell 6	4-34
4-19 Inflow and Outflow Weekly Average for Total Phosphorous, Total Dissolved Phosphorous, Total Dissolved Phosphorous, and Total Particulate Phosphorous for MWTS South Test Cell 7	4-35
4-20 General Water Quality Trends for Inflow Versus Outflow Concentrations for North and South Test Cells	4-37
4-21 (A) Time series of TP inflow and outflows for NTCs over treatment period April through December 2000, (B) TP time series for final 4 months of treatment period	4-39
4-22 (A) Time series of SRP inflow and outflows for NTCs over treatment period April through December 2000 (B) SRP time series for final 4 months of treatment period	4-40
4-23 (A) Time series of TDP inflow and outflows for NTCs over treatment period April through December 2000. (B) TDP time series for final 4 months of treatment period	4-41
4-24 (A) Time series of TP inflow and outflows for STCs over treatment period April through December 2000. (B) TP Time series for final 4 months of treatment period	4-42
4-25 (A) Times series of SRP inflow and outflows for STCs over treatment period April through December 2000. (B) SRP time series for final 4 months of treatment period	4-43
4-26 (A) Time series of TDP inflow and outflows for STCs over treatment period April through December 2000. (B) TDP time series for final 4 months of treatment period	4-44
4-27 Boxplot Summaries of TP inflows and Outflows to Wetlands in Control Cell and Treatment Cells, Over Final Four Months of Testing.....	4-45
4-28 Boxplot Summaries of TDP inflows and Outflows to Wetlands in Control Cell and Treatment Cells, Over Final Four Months of Testing.....	4-46

Exhibits	Page
4-29	Boxplot Summaries of SRP inflows and Outflows to Wetlands in Control Cell and Treatment Cells, Over Final Four Months of Testing.....
4-30	MWTS Test Cell Mass Balance Phosphorous and Nitrogen Summary
4-31	MWTS Test Cell Mass Balance Phosphorous Summary
4-32	Total Phosphorous Mass Removal in the MWTS Test Cells
4-33	Total Particulate Mass Removal in the MWTS Test Cells.....
4-34	Total Dissolved Mass Removal in the MWTS Test Cells
4-35	Dissolved Organic Phosphorous Mass Removal in the MWTS Test Cells.....
4-36	Soluble Reactive Mass Removal in the MWTS Test Cells.....
4-37	Total Nitrogen Mass Removal in the MWTS Test Cells.....
4-38	Total Kjeldahl Nitrogen Mass Removal in the MWTS Test Cells
4-39	Nitrate+Nitrate-Nitrogen Mass Removal in the MWTS Test Cells.....
4-40	Organic Nitrogen Mass Removal in the MWTS Test Cells.....
4-41	Ammonia Nitrogen Mass Removal in the MWTS Test Cells
4-42	Parameter values and significance information for regression of TP concentrations, NTC and STC sites.....
4-43	Results of Regression analysis of Total Phosphorous (TP) data Calibration and Treatment Periods
4-44	Robust Regression for Total Phosphorous (TP)
4-45	Analysis of Covariance Results for Total Phosphorous
4-46	Predicted Minus Observed Values of Soluble Reactive Phosphorous (SRP) for the Treatment Period
4-47	Comparison of TP Discharge Concentrations, North Test Cells
4-48	Parameter Values and Significance Information for Regression of SRP Concentrations, NTC and STC Sites
4-49	Results of Regression Analysis for Soluble Reactive Phosphorous, NTC and STC Sites
4-50	Robust Regressions for Soluble Reactive Phosphorous (SRP)
4-51	Analysis of Covariance of SRP Concentrations in Paired Watersheds.....
4-52	Predicted Minus Observed Values of Soluble Reactive Phosphorous (SRP) for Treatment Period.....
4-53	Comparison of SRP Discharge Concentrations, Treatment Period, NTC and STC Cells.....
4-54	Parameter Values and Significance Information for Regression of TDP Concentrations, NTC and STC Sites
4-55	Calibration and Treatment Equations for TDP in NTC-Control versus NTC-FeCl, NTC-Control versus NTC-PACL, and STC-Control versus STC-PACL
4-56	Robust Regressions for Total Dissolved Phosphorous (TDP).....
4-57	Analysis of Covariance, TDP Concentrations in Paired Watersheds.....
4-58	Predicted minus observed values of total dissolved Phosphorous (SRP) for the Treatment Period
4-59	Summary of Paired Watershed Analysis

Exhibits	Page
4-60A Treatment and Calibration Period Regressions for Outflow TKN Concentrations	4-95
4-60B Treatment and Calibrations Period Regressions for Outflow Alkalinity Concentrations	4-96
4-60C Treatment and Calibration Period Regressions for Outflow Aluminum Concentrations	4-97
4-60D Treatment and Calibration Period Regressions for Outflow Calcium Concentrations	4-98
4-60E Treatment and Calibration Period Regressions for Outflow Chloride Concentrations	4-99
4-60F Treatment and Calibration Period Regressions for Outflow Iron Concentrations.....	4-100
4-60G Treatment and Calibration Period Regressions for Outflow Magnesium Concentrations.....	4-101
4-60H Treatment and Calibration Period Regressions for Outflow Sulfate Concentrations.....	4-102
4-60I Treatment and Calibration Period Regressions for Outflow TDS Concentrations	4-103
4-60J Treatment and Calibration Period Regressions for Outflow TOC Concentrations.....	4-104
4-61A ANCOVA Results for Other Chemical Analytes	4-105
4-61B ANCOVA Results for Other Chemical Analytes	4-106
4-61C ANCOVA Results for Other Chemical Analytes	4-107
4-61D ANCOVA Results for Other Chemical Analytes	4-108
4-61E ANCOVA Results for Other Chemical Analytes	4-109
4-61F ANCOVA Results for Other Chemical Analytes	4-110
4-61G ANCOVA Results for Other Chemical Analytes	4-111
4-61H ANCOVA Results for Other Chemical Analytes	4-112
4-61I ANCOVA Results for Other Chemical Analytes	4-113
4-61J ANCOVA Results for Other Chemical Analytes	4-114
4-62 Summary of Results for the 7-Day Chronic Toxicity Test with <i>C. leedsii</i> and <i>C. dubia</i> initiated December 14 and 15, 2000.....	4-118
4-63 Results for the 96-Hour Chronic Toxicity Tests with <i>S. capricornutum</i> , Initiated December 19, 2000	4-118
4-64 Summary of Results for the 14-Day AGP Test with <i>S. capricornutum</i> , Initiated December 19, 2000	4-119
4-65 Toxicity Characteristic Leaching Procedure (TCLP) for Samples Collected on December 20, 2000 from the NTC 2,4 and STC 7	4-120
4-66 Water Quality Data for Samples Collected on December 20, 2000 for TCLP Analysis from NTC 2,4, and STC 7	4-121
4-67 MWTS Test Cell Sediment Data Summary, September, 1999 - January, 2001	4-123
4-68 Sediment Core Data from MWTS, NTC 2	4-125
4-69 Sediment Core Data from MWTS, NTC 3	4-126
4-70 Sediment Core Data from MWTS NTC 4	4-127

Exhibits	Page
4-71 Sediment Core Data from MWTS STC 6	4-128
4-72 Sediment Core Data from MWTS STC 7	4-129
4-73 Wetland Water Levels over 24 hour Period Following Cessation of Pumping	4-130
5-1 Calculation Data for Conversion of Concentration Data (mg/L) to Millequivalents Per Liter (meq/L)	5-1
5-2 Summary of Significant Differences Between Stations by Multiple Means Comparison for Treatment Period April through December, 2000	5-3
5-3 Radial Plot for NTC 2 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-8
5-4 Schoeller Plot for NTC 2 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-9
5-5 Radial Plot for NTC 3 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-10
5-6 Schoeller Plot for NTC 3 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-11
5-7 Radial Plot for NTC 4 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-12
5-8 Schoeller Plot for NTC 4 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-13
5-9 Radial Plot for STC 6 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-14
5-10 Schoeller Plot for NTC 6 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-15
5-11 Radial Plot for STC 7 Showing Concentrations of Ionic Parameters in meq/L for the Calibration Period	5-16
5-12 Schoeller Plot for NTC 7 Showing Concentrations of Ionic Parameters in meq/L During the Calibration Period	5-17
5-13 Radial Plot for NTC 2 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period	5-18
5-14 Schoeller Plot for NTC 2 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period	5-19
5-15 Radial Plot for NTC 3 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period	5-20
5-16 Schoeller Plot for NTC 3 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period	5-21
5-17 Radial Plot for NTC 4 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period	5-22
5-18 Schoeller Plot for NTC 4 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period	5-23
5-19 Radial Plot for STC 6 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period	5-24
5-20 Schoeller Plot for STC 6 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period	5-25

Exhibits	Page
5-21 Radial Plot for STC 7 Showing Concentrations of Ionic Parameters in meq/L During the Treatment Period.....	5-26
5-22 Schoeller Plot for STC 7 Showing Concentrations of Ionic Parameters During the Treatment Period.....	5-27
5-23 Radial Plot Comparing Inflow vs. Outflow for the NTCs During the Calibration Period in meq/L	5-28
5-24 Schoeller Plot Comparing Inflow vs. Outflow for the NTCs During the Calibration Period	5-29
5-25 Radial Plot Comparing Inflow vs. Outflow for the STCs During the Calibration Period in meq/L	5-30
5-26 Schoeller Plot Comparing Inflow vs. Outflow for the STCs During the Calibration Period	5-31
5-27 Radial Plot Comparing Inflow vs. Outflow in the NTCs During the Treatment Period in meq/L.....	5-32
5-28 Schoeller Plot Comparing Inflow vs. Outflow for the NTCs During the Treatment Period.....	5-33
5-29 Radial Plot Comparing Inflow vs. Outflow in the STCs During the Treatment Period in meq/L	5-34
5-30 Schoeller Plot Comparing Inflow vs. Outflow for the STCs During the Treatment Period.....	5-35
5-31 Radial Plot Comparing Inflow vs. Plant Effluent in the NTCs During the Treatment Period in meq/L.....	5-36
5-32 Schoeller Plot Comparing Inflow vs. Plant Effluent for the NTCs During the Treatment Period.....	5-37
5-33 Radial Plot Comparing Inflow vs. Plant Effluent in the STCs During the Treatment Period in meq/L.....	5-38
5-34 Schoeller Plot Comparing Inflow vs. Plant Effluent for the STCs During the Treatment Period.....	5-39
5-35 Radial Plot Comparing Inflow vs. Outflow for NTC 2 During the Calibration and Treatment Periods in meq/L	5-40
5-36 Schoeller Plot Comparing Inflow vs. Outflow for NTC 2 During the Calibration and Treatment Periods	5-41
5-37 Radial Plot Comparing Inflow vs. Outflow for NTC 3 During the Calibration and Treatment Periods in meq/L	5-42
5-38 Schoeller Plot Comparing Inflow vs. Outflow for NTC 3 During the Calibration and Treatment Periods	5-43
5-39 Radial Plot Comparing Inflow vs. Outflow for NTC 4 During the Calibration and Treatment Periods in meq/L	5-44
5-40 Schoeller Plot Comparing Inflow vs. Outflow for NTC 4 During the Calibration and Treatment Periods	5-45
5-41 Radial Plot Comparing Inflow vs. Outflow for STC 6 During the Calibration and Treatment Periods in meq/L	5-46
5-42 Schoeller Plot Comparing Inflow vs. Outflow for STC 6 During the Calibration and Treatment Periods	5-47

Exhibits	Page
5-43 Radial Plot Comparing Inflow vs. Outflow for STC 7 During the Calibration and Treatment Periods in meq/L	5-48
5-44 Schoeller Plot Comparing Inflow vs. Outflow for STC 7 During the Calibration and Treatment Periods	5-49
5-45 Radial Plots showing the chemical composition of the Water Conservation Areas	5-50
5-46 Schoeller Plots showing the chemical composition of the Water Conservation Areas	5-51
5-47 NTC Standard Error Plots for Alkalinity During the Treatment Period	5-52
5-48 STC Standard Error Plots for Alkalinity During the Treatment Period	5-53
5-49 NTC Standard Error Plots for Aluminum for Treatment Period	5-54
5-50 STC Standard Error Plots for Aluminum for Treatment Period	5-55
5-51 NTC Standard Error Plots for Calcium for Treatment Period	5-56
5-52 STC Standard Error Plots for Calcium for Treatment Period	5-57
5-53 NTC Standard Error Plot for Chloride for Treatment Period	5-58
5-54 STC Standard Error Plot for Chloride for Treatment Period	5-59
5-55 NTC Standard Error Plots for Iron Treatment Period	5-60
5-56 STC Standard Error Plots of Iron for Treatment Period	5-61
5-57 NTC Standard Error Plots for Magnesium for Treatment Period	5-62
5-58 STC Standard Error Plots for Magnesium for Treatment Period	5-63
5-59 NTC Standard Error Plots for Sulfate for Treatment Period	5-64
5-60 STC Standard Error Plots for Sulfate for Treatment Period	5-65
5-61 NTC Standard Error Plots for TDS for Treatment Period	5-66
5-62 STC Standard Error Plots for TDS for Treatment period	5-67
5-63 NTC Standard Error Plots for TOC for Treatment Period	5-68
5-64 STC Standard Error Plots for TOC for Treatment period	5-69
5-65 NTC Standard Error Plots of pH during the Treatment Period	5-70
5-66 STC Standard Error Plots of pH during the Treatment Period	5-71
5-67 NTC Standard Error Plot for Total Phosphorous for Treatment Period	5-72
5-68 STC Standard Error Plot for Total Phosphorous for Treatment Period	5-73
5-69 NTC Standard Error Plot for Total Phosphorous for Treatment Period	5-74
5-70 STC Standard Error Plot for Total Dissolved Phosphorous for Treatment Period	5-75
5-71 NTC Standard Error Plot for Soluble Reactive Phosphorous for Treatment Period	5-76
5-72 STC Standard Error Plot for Soluble Reactive Phosphorous for Treatment Period	5-77
5-73 NTC Standard Error Plot for TKN for Treatment Period	5-78
5-74 STC Standard Error Plot for TKN for Treatment Period	5-79
6-1 Pilot Unit Solids Monitoring Points	6-4

Appendix A
Laboratory Prescreening for Chemical Selection

dkAppendix B
Testing Polyaluminum Chloride

Appendix C

Trace Study Data

Appendix D
Description of the Big Cypress Seminole
Indian Reservation Demonstration Pilot

Appendix E

Water Regime Time Series Charts

Appendix F

Water Quality Time Series Charts

Appendix G
Water Quality Gradient Time Series Charts

Appendix H

Paired Watershed Regression Analysis

Appendix I

Toxicity Test Report

Appendix J
ENR Chemical Treatment Unit Design

Appendix K
North Test Cell Pilot Unit Evaluation

Appendix L
Operation Records for ENR Pilot Units
