

Everglades Restoration Update

Tommy Strowd, P.E.
Assistant Deputy Executive Director

Governing Board Workshop July 9, 2008

sfwmd.gov





C-111 Spreader Canal Project Expedited Construction

July 9, 2008
Governing Board Workshop

Tommy B. Strowd, P.E. – Assistant Deputy Executive Director Dewey Worth – Dir. Southern Everglades Everglades Restoration Resource Area






Existing System



- Flows are moved from north to south in the C-111 Canal for water supply and flood contol
 - To accomplish this ,stages are 'Stair-Stepped' down to sea level at S-197
- Environmental deliveries from C-111 are pumped at S-332D to supplement flows in Taylor Slough
 - Keeping water levels in the Slough higher than the C-111 canal
- This results in the significant loss of water from Taylor Slough to C-111 via underground seepage

Conceptual Solution




- Objectives
 - Reduce seepage losses
 - Keep water in Taylor Slough
 - Increase delivery of freshwater to Florida Bay and reduce salinity
 - Maintain current level of flood protection
- Concept
 - Divert excess water from C-111
 - 'Build' an underground 'mound' of water between the Slough and the canal
 - Reduce seepage from the Slough
 - Seepage would continue from the mound


Expedited Plan Components of PIR Alt 2D



Performance Summary



Ecosystem Benefits and Concern Areas



Stakeholder Comments

- Farming interest concerned increased water level controls will cause flooding
 - Allow lower canal stages upstream (S-177) to provide more water for Taylor Slough and provide some flood control benefit
 - Lower canal stages upstream could introduce water quality problems
- Environmental community supports higher water level controls to increase Taylor Slough flow and restore Florida Bay
 - Concerns regarding incremental implementation
- Purpose of PIR-1 should be to used to determine flows required to restore Taylor Slough
- Existing South Dade system has diminished flood control protection
- S-332D Seepage return should be addressed if possible to improve Taylor Slough water delivery

Linking Operations and Ecosystem Benefits

- Proposed structures facilitate a wide range of operational possibilities -- flexibility
- Establish base set of operations commensurate with benefits and constraints of the project
- Project Implementation Report (PIR) to include flexibility to test and measure benefits of different operating regimes
- Extensive monitoring
- Implement permanent operational changes in Phase 2 PIR along with any required mitigation measures if necessary


Opportunities / Challenges


- Expedited plan provides significant learning
- Early benefits and identification of potential problems
- Provides early design basis for PIR-2
- Working with USACE to maintain consistency

Questions

USACE PIR Recommended Plan – Alt 2D







Expedited Plan Recommendation