

Summary Report

Four-Week Test of Pump Station S-332D

August 30, 1999 to September 27, 1999



South Florida Water Management District

August 2000

Submitted to:

Florida Department of Environmental Protection

TABLE OF CONTENTS

LIST OF FIGURES.....	III
LIST OF TABLES	V
INTRODUCTION.....	1
ANTECEDENT CONDITIONS.....	2
OPERATIONS	5
OBJECTIVES.....	5
Proposal to FDEP	5
Concurrence Agreement.....	5
Real-Time Consultation.....	6
SUMMARY OF OPERATIONS	6
Week 1: August 30 - September 5.....	8
Week 2: September 6 - 12.....	10
Test Suspended: September 13-15	12
Week 3: September 16-19.....	13
Week 4: September 20-27.....	15
HYDROLOGY.....	19
RAINFALL.....	19
Regional Storms	19
County-Wide Rainfall.....	20
Local Rainfall.....	20
WATER LEVEL.....	21
Water Level at G-789, C-111 Basin north of S-176.....	21
Drawdown in L-31N Due to Pumping at S-332D.....	22
Target Stage for L-31W	23
Water Level in Taylor Slough Marsh	25
COMPUTED FLOW	26
Pump Station S-332D.....	26
Seepage Pattern into Frog Pond.....	28
Overflow from L-31W Canal to Taylor Slough.....	30
Flow at Taylor Slough Bridge.....	31
DISCHARGE MEASUREMENTS IN L-31W	32
Estimated Seepage from the L-31W Canal.....	33
Discharge Rating for the S-332D Pump Station	33
VELOCITY MEASUREMENTS IN TAYLOR SLOUGH	36
SURFACE WATER QUALITY.....	39
BACKGROUND AND OBJECTIVE.....	39
METHODS	39
Water Quality Data Sources	39
Quality Assurance.....	42
Detection Levels	42
Class III Water Quality Standards	42
Data Evaluation Methods	42
RESULTS OF NUTRIENT, PHYSICAL PARAMETER, AND TRACE METALS MONITORING.....	43
Class III Criteria Excursion Analysis	43
Dissolved Oxygen.....	44
Turbidity	44

Total Phosphorous	47
Nitrogen Species	48
Trace Elements	48
PESTICIDES	63
QUALITY ASSURANCE EVALUATION	64
SYNTHESIS	73
WATER QUALITY ISSUES	73
RELATIONSHIPS BETWEEN WATER QUALITY PARAMETERS OF CONCERN	74
Dissolved Oxygen	74
Turbidity	74
Total Phosphorous	77
FINDINGS	85
STRUCTURAL	85
HYDROLOGY	85
OPERATIONS.....	86
LOGISTICS.....	87
WATER QUALITY	87
PESTICIDES.....	88
SYNTHESIS.....	88
RECOMMENDATIONS	91
GLOSSARY.....	93
APPENDIX	
A. DOCUMENTS	
Proposal for Preliminary Operation of Pump Station S-332D	A-1
Cooperative Agreement	A-12
B. SFWMD WATER QUALITY DATA BY GRAB SAMPLING	
C. USACE WATER QUALITY DATA BY GRAB SAMPLING	
D. USACE TOTAL PHOSPHOROUS CONCENTRATION DATA BY AUTOSAMPLER	
E. SFWMD WATER QUALITY STATISTICS BY GRAB SAMPLING	
F. USACE WATER QUALITY STATISTICS BY GRAB SAMPLING	
G. CLASS III CRITERIA REFERENCE TABLE	

LIST OF FIGURES

Figure 1. Aerial view of S-332D and nearby features.....	1
Figure 2. Location of Water Level Monitoring Sites and Approximate Water Level Immediately Prior to Pump Test.....	4
Figure 3. Schematic of flows and stages before and during the pump test	7
Figure 4. Operation of S-332D during Week 1	9
Figure 5. Operation of S-176 during Week 1.....	10
Figure 6. Water level and target in the L-31W canal during Week 1	10
Figure 7. Operation of S-332D during Week 2.....	11
Figure 8. Water level and rainfall-driven target in the L-31W canal during Week 2	11
Figure 9. Operation in L-31W canal during Hurricane Floyd drawdown.....	13
Figure 10. Operation of S-332D during Week 3.....	14
Figure 11. Water level in L-31W and Week 3 target for overflow.	14
Figure 12. Water control structure flows into and out of L-31W during Week 4.....	16
Figure 13. Operation of S-176 and S-332D during Week 4	17
Figure 14. Tropical Storm Harvey making landfall in southwest Florida.....	19
Figure 15. Daily Sum of Rainfall at S-174	20
Figure 16. Water levels and rain in the vicinity of G-789	21
Figure 17. Head (slope) in the lower L-31N canal vs. gravity flow and pump flow.....	23
Figure 18. Stage L-31W: Target vs. Test.....	25
Figure 19. Water Levels in Taylor Slough compared to L-31W canal stage.....	26
Figure 20. S-332D Computed Flow.....	27
Figure 21. Water Level at FROGP1 compared to canals and local rain	28
Figure 22. Water Level at FROGP compared to canals and local rain	29
Figure 23. Water level at FROGP2 compared to canals and local rain.....	29
Figure 24. Flow at Taylor Slough Bridge.....	32
Figure 25. Plan View of Stream Gauging Site	35
Figure 26. Monitoring sites for marsh velocity.....	37
Figure 27. Water Quality Monitoring Locations for District and USACE Sampling Activities.....	41
Figure 28. Dissolved Oxygen Levels monitored by the District at S-332D (S176)	45
Figure 29. Dissolved Oxygen Levels monitored by the District at S-332	45
Figure 30. Turbidity Measurements at the District Monitoring Site for S-332D (S176).....	46
Figure 31. Turbidity Measurements at the District Monitoring Site for S-332	46
Figure 32. Comparison of TP Concentrations and Median Values from a. USACE and b. SFWMD Grab Sampling Locations	49
Figure 33. Total Phosphorus collected by Grab sampling and Autosamplers at the S-331 monitoring location.....	50
Figure 34. S-196 and S-194 Flows Compared with TP Concentration for C102L31N and C103L31N.....	51
Figure 35. S-332D and S-174 Flow and Upstream TP Concentrations.....	52
Figure 36. S-332D and S-174 Flow and Downstream TP Concentrations for S332DW and the Taylor Slough Marsh Site, L31WTS	53
Figure 37. S-332 Flow and Upstream TP Concentration.....	54

Figure 38. S-175 Flow and Upstream TP Concentrations	55
Figure 39. Comparison of TN Concentrations and Median Values from a. USACE and b. SFWMD Grab Sampling Locations	56
Figure 40. Comparison of TKN Concentrations and Median Values from a. USACE and b. SFWMD Grab Sampling Locations	57
Figure 41. Comparison of NO ₃ Concentrations and Median Values from a. USACE and b. SFWMD Grab Sampling Locations	58
Figure 42. Comparison of ON Concentrations and Median Values from a. USACE and b. SFWMD Grab Sampling	59
Figure 43. Comparison of Ammonium Concentrations and Median Values from a. USACE and b. SFWMD Grab Sampling Locations	60
Figure 44. Comparison of Un-ionized Ammonia Concentrations (mg/L as NH ₃) and Median Values from a. USACE and b. SFWMD Grab Sampling Locations	61
Figure 45. S-332D Pump Test Data for Pesticides at S331	66
Figure 46. S-332D Pump Test Data for Pesticides at S176	67
Figure 47. S-332D Pump Test Data for Pesticides at S332	68
Figure 48. S-332D Pump Test Data for Pesticides at S-175	69
Figure 49. Time Series Plot of Rain vs. Turbidity at S-332 and S-332D	76
Figure 50. Correlation of S-332D Flow and Turbidity at S-332D.....	76
Figure 51. Correlation of-332D Flow and Turbidity Downstream at S-332.....	76
Figure 52. Concentration of total phosphorous along the L-31N and L-31W canals during the pump test.....	79
Figure 53. TP Concentrations observed during Start of S-332D Pump Test.....	82
Figure 54. S-332D Flow and Upstream Autosampler TP	82
Figure 55. S-332D Flow vs. Downstream Autosampler TP	82
Figure 56. TP concentrations and water levels near L-31W.....	83

LIST OF TABLES

Table 1. L-31W Projected Target Stage	24
Table 2. Summary of S-332D Flow	27
Table 3. Depth and velocity measurements on L-31W west road.....	30
Table 4. Rough Estimate of Rate of Overflow	31
Table 5. Discharge Measurements.....	33
Table 6. GPS coordinates for the five sample sites located west of the L-31W canal.....	37
Table 7. Mean velocity measurements for the five sampling sites west of L-31W canal.....	38
Table 8. Resultant vector magnitude and direction for each site measured	38
Table 9. Summary of Surface Water Quality Monitoring Locations and Method of Sampling .	40
Table 10. Description of the notched box and whisker plot used in this report	47
Table 11. Representative minimum detection limits (MDL) and practical quantitation limits (PQL) for pesticides determined during the S332D pump test	65
Table 12. Selected properties of pesticides detected during the S332D pump test sampling events.....	70
Table 13. Toxicity of pesticides detected during the S332D pump test sampling events to selected freshwater aquatic invertebrates and fishes (ug/L).....	71
Table 14. Summary of Atrazine Detections	72
Table 15. Summary of Hexazinone Detections	72

INTRODUCTION

S-332D is a pump station located near the junction of the L-31N and L-31W canals (see **Figure 1**), west of Homestead, Florida. It is rated for 568 cfs, 500 cfs diesel and 68 cfs electric. It was constructed by the U.S. Army Corps of Engineers and conveyed to the South Florida Water Management District in December 1997. Its purpose was to increase flows from the L-31N canal toward Taylor Slough and Florida Bay, and to maintain flood protection for the C-111 Basin. Its implementation was planned as part of the Experimental Program of Water Deliveries to Everglades National Park, Test Iteration 7, Phase II. Under this phase of the Experimental Program, use of S-332D was intended to promote overland flow of water into Taylor Slough by raising canal stages in the L-31W canal, allowing overbank flow to mimic more natural sheetflow into Everglades National Park. The South Florida Water Management District (SFWMD) applied for a general permit with the Florida Department of Environmental Protection. However, issues raised by interested parties during the permit process caused the application to remain incomplete through several extensions.




Figure 1. Aerial view of S-332D and nearby features

In light of the difficulties to permanently implement the operation of S-332D, SFWMD proposed a short-term, focused field experimentation that could begin to address the issues raised in the permit process. The operational objectives of the test were to raise water levels in the L-31W

canal to meet or exceed a rainfall-driven target, and to allow canal water to overflow into the Taylor Slough marsh.

Intensive monitoring of hydrologic and water quality parameters was conducted. With the data, a preliminary assessment of this operation is presented in this report. Operational experience was gained on the flexibility and limitations of the use of S-332D. The information obtained from the pump test is a first step in the development of more comprehensive testing of S-332D and wider-scale monitoring of its effects, with the eventual goal of implementing its operation as part of the C-111 and Modified Water Deliveries projects.

ANTECEDENT CONDITIONS

Hurricane Dennis skirted the coast of South Florida between August 26-28, immediately prior to the start of the pump test. Canals were lowered in anticipation of heavy rain, which didn't materialize. Had this category 2 storm made landfall in South Florida, the damage could have been extensive. Dennis dropped 19 inches of rain in North Carolina and caused \$157 million in damages.

The antecedent rainfall conditions were at the high end of the normal range. The rainfall for Miami-Dade for the month of June was 141% of normal. July was 83% of normal and August was 128% of normal. The rainfall for the wet season up to the beginning of the pump test totaled 26.94 inches, or 120% of the 30-year mean.

Figure 2 shows the location of canals L-31N, L-31W, and C-111. The canal water levels prior to the pump test were within the operating ranges specified under Test 7 Phase 1. The water level upstream of S-176 was 4.8 ft. The operational range for the L-31N canal upstream of S-176 is 4.75 ft to 5.0 ft. The water level upstream of S-177 was 3.7 ft. The operational range for the C-111 canal upstream of S-177 is 3.6 ft to 4.2 ft. Finally, the water level upstream of S-175 was 4.6 ft, which is below the maximum of 4.7 ft for the rainfall-driven target in the L-31W canal.

The groundwater gradient, indicating the direction of groundwater flow in the area, presented a typical west-to-southeast slope. Three transects were used to assess the antecedent conditions of groundwater gradients in the area. **Figure 2** shows the location of the transects and the water levels along those transects prior to the pump test. For simplicity in describing the conditions prior to the pump test, the water level was computed as the average of the 24 hours preceding the pump test, rounded off to the nearest 1/10 of a foot. Water levels in three locations were considered for the area south of S-331: G-3437, L-31N between S-331 and L31NT, and Humble with values of 6.1, 5.0, and 4.8 ft, respectively. The slope along this transect indicates a groundwater gradient from Rocky Glades to the L-31N canal, and from the L-31N canal to the C-111 basin. Three gages were considered for the area north of S-176: Rutzke, S-176 HW, and G-789 with values of 5.5, 4.8, and 4.0 ft, respectively. This transect indicates a groundwater gradient from Rocky Glades to the L-31N canal, and from the L-31N canal to the C-111 basin. The C-113 canal may also influence gage G-789, causing a more southerly gradient near the gage. Finally, water levels at seven locations were considered in the Frog Pond vicinity: NTS1,

L-31W between S-174 and S-175, FROGP1, FROGP, FROGP2, C-111 between S-176 and S-177, and Robblee with values of 5.3, 4.6, 4.7, 4.2, 3.8, 3.7, and 3.6 ft, respectively. The antecedent conditions near the Frog Pond, as indicated by these water levels, showed a groundwater gradient from the Taylor Slough marsh to the L-31W canal, from the Frog Pond to the L-31W canal, from the Frog Pond to the C-111 canal, and from the C-111 canal to the C-111 basin.




Figure 2. Location of Water Level Monitoring Sites and Approximate Water Level Immediately Prior to Pump Test. (gw=groundwater, hw=headwater, tw=tailwater)