

# TOC MEETING

## CEPP SOUTH CONTRACT 2a S356E Pump Station S334E Spillway

January 18, 2022

Savanna Royals  
savanna.d.royals@usace.army.mil



**BUILDING STRONG®**

**US ARMY CORPS OF ENGINEERS | JACKSONVILLE DISTRICT**






# Project Overview

## ■ CEPP


- Purpose improve QQTD of water to Northern Estuaries, central Everglades, ENP, and Florida Bay
- Authorized in WRDA 2016



# CEPP South Overview

## ■ CEPP South

- CNT 1: L-67A Culverts (S-631, S-632 & S-633)
  - L-67C Levee Degrade 8 miles and Gap 6,000-ft
  - Fill Ag Ditches between A and C
- ✓ CNT 2A: S-356E Pump Station 1,000 cfs
  - S-334E Gated Spillway 1,200 cfs
- CNT 2B: Demolish S-356, add recreation
- CNT 3A: S-333N Spillway 1,150 cfs
- CNT 3B: S-355W Spillway 1,230 cfs
- CNT 5: L-67D Blue Shanty Levee 8 miles
- CNT 6: L-29 Levee Degrade 4 miles
  - L-67 Ext Levee Degrade, Canal Backfill 5.5 miles
- CNT 14: Old Tamiami Trail Removal 5.45 miles





# CEPP-S Contract 2a Overview

- **Construction Award FY23— 4 years**


- **S356E**

- 1,000 cfs capacity
- 6 bays
  - 4 diesel pumps (250 cfs each)
  - 2 electric pumps (125 cfs each)

- L29 levee realignment


- **S334E**

- 1,200 cfs capacity
- ~28 ft across L29 canal





# Water Quality Monitoring Plan



# CERPRA Compliance Water Quality Monitoring Plan

Station	Collection Method	Frequency	Parameter TESTS
S356E <sup>1</sup> S334E	Grab	Biweekly Recorded Flow (BWRF)	Total Nitrogen (TN), Total Phosphorus (TP)
	In-situ Grab	BWRF	Dissolved Oxygen (DO), pH (PH), Specific conductance (SCOND), Temperature (TEMP)

<sup>1</sup>This station will be collected by SFWMD on the same day as monitoring at Shark River Slough stations for the Consent Decree Appendix A compliance calculation.

The existing S356/S334 Stations will continue to be sampled during construction.





# Questions

