

Disclaimer: Information contained in the report addresses environmental conditions only and is not the official South Florida Water Management District operations recommendation or decision.

M E M O R A N D U M

TO: John Mitnik, Assistant Executive Director, Executive Office Staff

FROM: SFWMD Staff Environmental Advisory Team

DATE: February 25, 2026

SUBJECT: Weekly Environmental Conditions for Systems Operations

Summary

Weather Conditions and Forecast

An upper-level trough currently located just east of Florida over the western Atlantic will continue lifting away today. In its wake, a strong surface high will shift directly over Florida tonight. Although the modified Arctic air mass behind the recent front is already beginning to moderate, the combination of clear skies, dry atmosphere, and light to calm winds will favor efficient radiational cooling again tonight. By Wednesday, the surface high will shift offshore into the western Atlantic, causing the low-level flow to veer to the south and southwest, beginning a warming trend across the region. With the continental air mass still in place and subsidence dominating, dry conditions are expected to persist through Thursday. A notable pattern change will occur late Thursday night as another upper-level disturbance digs southeastward into the northern Gulf Coast. As this feature amplifies west of Florida, south to southeast flow will strengthen across the region, allowing deeper moisture to begin returning northward potentially supporting isolated light showers along portions of the east coast late Thursday night. By Friday, the trough axis is forecast to remain just west of Florida. This location will favor continued low-level moisture transport, increasing instability, and enhanced upper-level divergence ahead of the trough. The resulting large-scale ascent, combined with a progressively more unstable environment, could support scattered to numerous heavy showers and thunderstorms developing over the eastern Gulf of Mexico Friday afternoon. As the system shifts eastward, storm activity could spread into the Kissimmee Valley and areas west and north of Lake Okeechobee after midnight Friday into early Saturday. There is some uncertainty in the timing of these features, which is why the Friday QPF is rated low confidence. As the upper disturbance crosses north Florida on Saturday, the steering flow over South Florida will veer southwesterly favoring development of most of the thunderstorm activity towards portions of the upper east coast during the afternoon hours. Due to the large lead time and complexity of this system, the Saturday QPF is also rated low confidence. By Sunday morning, the upper trough is forecast to shift east of Florida. Subsidence on the backside of the system should promote drier conditions. However, as the upper-level system departs, it will send a trailing surface front southward where it will stall over south Florida. Northeasterly winds behind the boundary, combined with shallow moisture along and just

north of the front, could support isolated to widely scattered light showers along parts of the east coast Sunday into Monday. For the 7-day period ending next Tuesday morning, above-average total SFWMD rainfall remains possible.

Kissimmee

In the past week, releases were made as needed from East Lake Toho and Lake Toho to continue snail kite nesting season stage recessions to reach low pool by June 1, 2026. Releases from KCH followed the Headwaters Revitalization Schedule (HRS) Increment 1 Temporary Deviation Discharge Plan. Weekly average discharge on February 22, 2026 was 350 cfs at S-65 and 290 cfs at S-65A. Mean weekly water depth on the Kissimmee River floodplain was unchanged from the previous week's value of 0.38 feet. The weekly average concentration of dissolved oxygen in the Kissimmee River decreased from the previous week's value of 9.6 mg/L to 9.2 mg/L, which is above both the potentially lethal level of 1.0 mg/L and the stressful level of 2.0 mg/L for Florida bass and other species (**Figure KB-6**).

Lake Okeechobee

Lake Okeechobee stage was 11.11 feet NAVD88 (12.41 ft NGVD29) on February 22, 2026, which was 0.15 feet lower than the previous week and 0.59 feet lower than a month ago. Average daily inflows (excluding rainfall) were similar to the previous week, 210 cfs. Average daily outflows (excluding evapotranspiration) increased from 2,300 cfs the previous week to 3,160 cfs. The most recent non-obscured satellite image from February 21, 2026, NOAA's Harmful Algal Bloom Monitoring System suggests moderate cyanobacteria activity from Fisheating Bay down to South Bay.

Estuaries

Total inflow to the St. Lucie Estuary averaged 86 cfs over the past week with no flow coming from Lake Okeechobee. Mean surface salinities increased at all sites within the estuary over the past week. Salinity in the middle estuary was in the upper stressed range (>25) for adult eastern oysters.

Total inflow to the Caloosahatchee River Estuary averaged 443 cfs over the past week with 230 cfs coming from Lake Okeechobee. Over the past week, surface salinities decreased at S-79 and increased at the remaining sites in the estuary. Surface salinities were in the optimal range (0-10) for tape grass in the upper estuary at S-79 and Val-75, and in the damaging range (>15) at Ft. Myers. Salinities were in the optimal range (10-25) for adult oysters at Cape Coral, and in the upper stressed range (>25) at Shell Point and Sanibel.

Stormwater Treatment Areas

For the week ending Sunday, February 22, 2026, 13,600 ac ft of Lake Okeechobee water was delivered to the FEBs/STAs. The total amount of Lake releases sent to the FEBs/STAs in WY2026 is approximately 83,200 ac-feet. The total amount of inflows to the STAs in WY2026 is approximately 581,000 ac-feet. Online STA treatment cells are at or near target stage. STA-1E Central Flow-way is offline for construction activities. STA-1W Eastern Flow-way is offline for vegetation management activities. STA 3/4 Central Flow-way is off-line for vegetation rehabilitation. Operational restrictions are in effect in STA-1E Western Flow-way, STA-2 Flow-ways 2, 3 and 4, and STA-3/4 Eastern Flow-way

for vegetation management activities. This week, if LOSOM recommends Lake releases to the WCAs and conditions allow, releases will be sent to STA-2, STA-3/4 and STA-5/6.

Everglades

Over the past week, the Everglades Protection Area (EPA) received little to no rainfall (**Table EV-1**). Continued recessions occur throughout the system with the average stage change at monitored sites approximately -0.10 ft/week. Southern WCA-2A stage is receding but remains unseasonably deep. In contrast most areas within WCA-3A, Everglades National Park (ENP), and WCA-1 continue to be very dry (below the 10th percentile). Below-average depths in WCA-3A and ENP have ecological effects including reducing the population sizes of already reduced prey populations, increasing the risk of damaging wildfire, promoting peat oxidation, and ridge/slough degradation. Wading bird activity remains limited, with small numbers foraging along the southwestern coast of ENP, WCA-1, and northern WCA-2A. Most major colonies across ENP and the WCAs remain inactive or have low nest numbers. Relatively small numbers of birds are nesting at Alley N and 6th Bridge colonies just north and south of I-75 in WCA-3A, while Cuthbert and Diamond colonies along the Florida Bay coastline remain active but with low numbers. Taylor Slough stages continued to drop last week and remain below the recent averages for this time of year by 9.5 inches. Average Florida Bay salinity increased last week and is above recent averages for this time of year by 6.5.

Supporting Information

Kissimmee Basin

Upper Kissimmee

On February 22, 2026, mean daily lake stages were 56.1 feet NAVD88 (0.9 feet below schedule) in East Lake Toho, 53.1 feet NAVD88 (0.9 feet below schedule) in Lake Toho, and 48.7 feet NAVD88 (2.6 feet below the Increment 1 Temporary Deviation schedule) in Lakes Kissimmee-Cypress-Hatchineha (KCH) (**Table KB-1, Figures KB-1-3**).

Lower Kissimmee

For the week ending February 22, 2026, mean weekly discharge was 350 cfs at S-65 and 290 cfs at S-65A. Mean weekly discharge from the Kissimmee River was 310 cfs at S-65D and 210 cfs at S-65E (**Table KB-2**). Mean weekly headwater stages were 45.2 feet NAVD88 at S-65A and 28.4 feet NAVD88 at S-65D. Mean weekly river channel stage decreased from the previous week's value of 31.0 feet to 30.9 feet NAVD88 (**Figure KB-4**). Mean weekly water depth on the Kissimmee River floodplain was unchanged from the previous week's value of 0.38 feet (**Table KB-2, Figure KB-5**). The weekly average concentration of dissolved oxygen in the Kissimmee River decreased from 9.6 mg/L the previous week to 9.2 mg/L (**Table KB-2, Figure KB-6**).

Water Management Recommendations

Continue the stage recessions in East Lake Toho and Lake Toho to reach their low pools on June 1, 2026. In KCH, follow the Headwaters Revitalization Schedule (HRS) Increment 1 Temporary Deviation Discharge Plan for S-65/S-65A (**Figure KB-7**). With KCH stage in Zone B3, target flows between 300 and 1,400 cfs at S-65A, using the Increment 1 Interpolation Tool to determine discharge relative to stage in KCH; if stage decreases into Zone B4, target flows of 300 cfs.

Table KB-1. Average discharge for the preceding seven days, Sunday’s average daily stage and Sunday’s average daily departure from Kissimmee Chain of Lakes (KCOL) flood regulation lines or temporary schedules. All data are provisional.

Water Body	Structure	Stage Monitoring Site	Weekly (7-Day) Average Discharge (cfs)	Sunday Lake Stage (feet NAVD88) ^a	Schedule Type ^b	Sunday Schedule Stage (feet NAVD88)	Sunday Departure from Regulation (feet)	
							2/22/26	2/15/26
Lakes Hart and Mary Jane	S-62	LKMJ	20	59.8	R	59.9	-0.1	0.0
Lakes Myrtle, Preston and Joel	S-57	S-57	9	60.0	R	60.0	0.0	0.0
Alligator Chain	S-60	ALLI	0	62.9	R	62.9	0.0	-0.1
Lake Gentry	S-63	LKGT	0	60.5	R	60.4	0.1	0.0
East Lake Toho	S-59	TOHOE	190	56.1	R	57.0	-0.9	-0.8
Lake Toho	S-61	TOHOW S-61	490	53.1	R	54.0	-0.9	-0.8
Lakes Kissimmee, Cypress and Hatchineha	S-65	KUB011 LKIS5B	350	48.7	T	51.3	-2.6	-2.9

a. Names of in-lake monitoring sites and structures used to determine lake stage. If more than one site is listed, an average is reported.

b. A: projected recession line; R: USACE regulation schedule; S: temporary recession target line; T: temporary schedule; NA: not applicable or not available.




Figure KB-1. East Lake Toho regulation schedule, stage, discharge, and rainfall.




Figure KB-2. Lake Toho regulation schedule, stage, discharge, and rainfall.




Figure KB-3. Lakes Kissimmee, Cypress and Hatchineha regulation schedule, stage, discharge, and rainfall.

Table KB-2. One- and seven-day average discharge and stage at Lower Kissimmee basin structures, river channel dissolved oxygen concentrations and water depths in the Phase I area floodplain. All data are provisional.

Metric	Location	Sunday Daily Average	Weekly Average for Previous Seven Day Periods			
		2/22/26	2/22/26	2/15/26	2/8/26	2/1/26
Discharge	S-65	360	350	340	340	410
Discharge	S-65A ^a	310	290	300	300	350
Headwater Stage (feet NAVD88)	S-65A	45.2	45.2	45.2	45.2	45.3
Discharge	S-65D ^b	330	310	330	330	400
Headwater Stage (feet NAVD88)	S-65D ^c	24.7	28.4	28.4	28.4	28.8
Discharge (cfs)	S-65E ^d	250	210	220	220	300
Discharge (cfs)	S-67	0	0	0	0	0
Dissolved Oxygen (mg/L) ^e	Phase I, II/III river channel	8.7	9.2	9.6	9.5	9.7
River channel mean stage (feet NAVD88) ^f	Phase I river channel	30.9	30.9	31.0	31.0	31.4
Mean depth (feet) ^g	Phase I & II/III floodplain	0.39	0.38	0.38	0.38	0.39

a. Combined discharge from main and auxiliary structures.

b. Combined discharge from S-65D, S-65DX1, and S-65DX2.

c. Average stage from S-65D and S-65DX1.

d. Combined discharge from S-65E and S-65EX1.

e. Dissolved oxygen is the average of values from sondes KRBN, PC62, PC33, PD62R, and PD42R.

f. Mean of five river channel stations (PC62, KRDR02, KRBN, PC33, PC11) in the Phase I area.

g. One-day spatial average obtained from the South Florida Water Depth Assessment Tool (SFWDAT).




Figure KB-4. Kissimmee River stage, discharge, and rainfall.







Figure KB-5. Phase I-II-III area Kissimmee River floodplain water depths (from left to right) one year ago, one month ago, and current.



Report Date: 2/24/2026; data are through: 2/22/2026



Figure KB-6. Kissimmee River channel mean daily dissolved oxygen concentration (mg/L), S-65A discharge (cfs), temperature (°C) and rainfall (inches). Dissolved oxygen (DO) and temperature are mean daily values averaged for PC62, KRDR02, KRBN, PC33, PC11, PD62R, and PD42R with an average of five stations reporting this week. Rainfall values are daily totals for Kissimmee River (Pool BCD) AHED watershed.

HRS Increment 1 Temporary Deviation Discharge Plan for S-65/S-65A

Discharge Guidance for Increment 1 Temporary Deviation Discharge Plan		
ZONE	S-65 RELEASES	S-65A TARGET FLOWS
ZONE A	Releases for Flood Risk Management up to maximum structure capacity as determined by downstream constraints with a firm capacity of 3,000 cfs.	
ZONE B1	1,400 cfs minimum ramp to 3,000 cfs at Zone A boundary	S-65A releases between 1,400 cfs and 3,000 cfs at Zone A boundary based on Table 1
ZONE B2	Releases as needed to target flows at S-65A	Target S-65A flows of 1,400 cfs to meet ecological needs
ZONE B3	Releases as needed to target flows at S-65A	S-65A flows between 300 cfs and 1,400 cfs
ZONE B4	Releases as needed to target flows at S-65A	Target S-65A flows of 300 cfs
ZONE B5	Releases as needed to target flows at S-65A	Target S-65A flows of 150 cfs
ZONE C	0 cfs	Flow as needed to maintain optimum S-65A headwater




Table KB-3. Maximum Rate of Change Limits for S-65A

MAXIMUM Release Rate of Change Limits for S-65A. In general recommended rates of change will be slower than shown in this table.

Q (cfs)	Maximum rate of INCREASE (cfs/day)	Maximum rate of DECREASE (cfs/day)
0-300	50	-50
301-650	75	-75
651-1400	150	-150
1401-3000	300	-600
>3000	1000	-2000

CENTRAL AND SOUTHERN FLORIDA PROJECT
 2024 LAKE KISSIMMEE, HATCHINEHA & CYPRESS
 Temporary Deviation (Increment 1)
 DATED: May 2024
 DEPARTMENT OF THE ARMY, JACKSONVILLE DISTRICT
 CORPS OF ENGINEERS, JACKSONVILLE, FLORIDA

Other Considerations

- When possible, limit lake ascension rate in the Jun 1 - Aug 15 window to 0.25 ft per 7 days in Lakes Kissimmee, Cypress, Hatchineha (S-65), East Toho (S-59) and Toho (S-61).
- If outlook is for extreme dry conditions meet with KB staff to discuss modifications to this plan.

Figure KB-7. Headwaters Revitalization Schedule (HRS) Increment 1 Temporary Deviation Discharge Plan for S-65/S-65A.

Lake Okeechobee

Lake Okeechobee stage was 11.11 feet NAVD88 (12.41 ft NGVD29) on February 22, 2026, which was 0.15 feet lower than the previous week and 0.59 feet lower than a month ago (**Figure LO-1**). Lake stage is in Zone D of the regulation schedule, is 0.52 feet above the water shortage management band (**Figure LO-2**) and is 1.47 feet below the ecological envelope (**Figure LO-3**). According to NEXRAD, 0.07 inches of rain fell directly over the lake during the previous week, and 1.04 inches were lost to evapotranspiration.

Average daily inflows (excluding rainfall) were similar to the previous week, 210 cfs. The only notable inflows came from the Kissimmee River (210 cfs via S-65E(X1)). Average daily outflows (excluding evapotranspiration) increased from the previous week, rising from 2,300 cfs to 3,160 cfs. The highest single structure release was to the south through the S-351 structure (1,070 cfs). **Figures LO-4 and LO-5** show the combined average daily inflows and outflows for the lake over the past eight weeks, and average inflows and outflows last week, respectively.

In the most recent non-obscured satellite image from February 21, 2026, NOAA's Harmful Algal Bloom Monitoring System suggests moderate cyanobacteria activity nearshore from Fisheating Bay down to South Bay (**Figure LO-6**).

Note: All data presented in this report are provisional and are subject to change.

1 Month Ago:
01/22/2026

Current:
02/22/2026

11.70 ft
NAVD88

11.11 ft
NAVD88




Figure LO-1. Lake Okeechobee water depth estimates based on South Florida Water Depth Assessment Tool (SFWDAT).




Figure LO-2. Recent Lake Okeechobee stages with projected stages based on a conditional position analysis.
 Note: stages are in NGVD29, approximate NAVD88 values are shown for reference.

Lake Okeechobee Stage vs Ecological Envelope




Figure LO-3. The current and select prior year's annual lake stage hydrographs in comparison to the Lake Okeechobee ecological envelope (light grey).




Figure LO-4. Major inflows (orange) to and outflows east and west (blue) from Lake Okeechobee. Outflows south are shown in green. Flows into Lake Okeechobee from the L-8 canal through S-271 (formerly Culvert 10A) or from the C-44 canal through the S-308 are included as inflows. Conversely, flows from Lake Okeechobee into the L-8 or C-44 canals are included with outflows. Inflows are shown as positive values; outflows are negative. Outflows through the S-77 (Caloosahatchee) and S-308 (C-44 Canal) structures are based on downstream gauges to include flows to lock openings for navigation.




Figure LO-5. Inflows into Lake Okeechobee from Indian Prairie basins, Taylor Creek/Nubbin Slough, Kissimmee River and Fisheating Creek (currently no flow data available for FECR), and outflows to the west via S-77, to the east via S-308, to the south via S-351, S-352, S-354, and to southeast via S-271 (formerly Culvert 10A) for the week of Feb 16 – 22, 2026.




Figure LO-6. Cyanobacteria bloom index level on Lake Okeechobee, based on NOAA’s harmful algal bloom monitoring system. Gray color indicates cloud cover. *Provisional NOAA image, subject to change*.

Estuaries

St. Lucie Estuary

Over the past week, mean total inflow to the St. Lucie Estuary was 86 cfs (**Figures ES-1 and ES-2**), and the previous 30-day mean inflow was 96 cfs. For comparison, the historical provisional mean inflows from contributing areas are shown in **Figure ES-2**.

Over the past week, surface salinities increased at all sites within the estuary (**Table ES-1 and Figure ES-3**). The seven-day moving average of the surface and bottom salinities at the US1 Bridge was 27.3. Salinity conditions in the middle estuary were estimated to be within the upper stressed range for adult eastern oysters (**Figure ES-4**). The mean larval oyster recruitment rate reported by the Fish and Wildlife Research Institute (FWRI) for January was 0.1 spat/shell at Rio, which is a decrease from the previous month (**Figure ES-5**).

Caloosahatchee River Estuary

Over the past week, mean total inflow to the Caloosahatchee River Estuary was 443 cfs (**Figures ES-6 and ES-7**), and the previous 30-day mean inflow was 385 cfs. For comparison, the historical provisional mean inflows from the contributing areas are shown in **Figure ES-7**.

Over the past week, surface salinities decreased at S-79 and increased at the remaining sites in the estuary (**Table ES-2 and Figures ES-8 and ES-9**). The seven-day mean salinities (**Table ES-2**) were within the optimal range (0-10) for tape grass in the upper estuary at S-79 and Val-75 but were in the damaging range (>15) at Fort Myers. The seven-day mean salinity values were within the optimal range for adult eastern oysters at Cape Coral and in the upper stressed range (>25) at Shell Point and Sanibel (**Figure ES-10**). The mean larval oyster recruitment rates reported by the FWRI in January were 0.05 spat/shell at Iona Cove and 0.03 spat/shell at Bird Island (**Figures ES-11 and ES-12**).

Surface salinity at Val I-75 was forecast for the next two weeks using an autoregression model (Qiu and Wan, 2013¹) coupled with a linear reservoir model for the tidal basin. Model scenarios included pulse releases at S-79 ranging from 450 to 2,000 cfs, with estimated tidal basin inflows of 47 cfs. Model results from all scenarios predict daily salinity to be 7.7 or lower and the 30-day moving average surface salinity to be 8.2 or lower at Val I-75 at the end of the two-week period (**Table ES-3 and Figure ES-13**). This keeps predicted salinities in the upper estuary within the optimal salinity range (0-10) for tape grass.

¹ Qiu, C., and Y. Wan. 2013. Time series modeling and prediction of salinity in the Caloosahatchee River Estuary. *Water Resources Research* 49:5804-5816.

Red Tide

The FWRI reported on February 20, 2026, that *Karenia brevis*, the Florida red tide dinoflagellate, was not observed at bloom concentrations in any samples collected within the District region.

Water Management Recommendations

Lake stage is in Zone D. Current climatological conditions are normal and hydrological conditions are dry. The LOSOM release guidance suggests up to 2,000 cfs release at S-79 to the Caloosahatchee River Estuary and no releases at S-80 to the St. Lucie Estuary.

Minimum Flows and Minimum Levels

The minimum flows and levels (MFL) for the Caloosahatchee River Estuary is a 30-day moving average flow of 457 cfs or greater at S-79. The current 30-day average flow at S-79 is 385 cfs (**Figure ES-14**) which is an exceedance.

The MFL for the Northwest Fork of the Loxahatchee River is a) flows at Lainhart Dam maintained at 35 cfs or greater and b) the 20-day moving average salinity of 2 or less at River Mile (RM) 9.2. An exceedance occurs when flows decline below 35 cfs for more than 20 consecutive days or when the 20-day moving average salinity at River Mile 9.2 exceeds 2. The current daily average flow at Lainhart Dam is 35 cfs (**Figure ES-15**) and the 20-day average salinity at RM 9.2 is 2.9 (**Figure ES-16**) which is an exceedance.




Figure ES-1. Basins, water control structures and salinity monitoring sites in the St. Lucie Estuary.




Figure ES-2. Total daily inflows from Lake Okeechobee and runoff from the C-44, C-23, C-24, Ten Mile Creek, and Tidal Basins into the St. Lucie Estuary.

Table ES-1. Seven-day mean salinity at oyster monitoring sites in the St. Lucie Estuary. Current means are in bold font; previous week's means are in parentheses. The envelope reflects the optimum salinity range for adult eastern oysters (*Crassostrea virginica*) in the estuary. Data are provisional.

Sampling Site	Surface	Bottom	Optimum Envelope
HR1 (North Fork)	24.6 (24.4)	25.5 (26.1)	10.0 – 25.0
US1 Bridge	27.3 (27.0)	27.3 (27.6)	10.0 – 25.0
A1A Bridge	31.9 (31.1)	32.3 (32.0)	10.0 – 25.0




Figure ES-3. Mean daily salinity at the A1A, US1, and HR1 sites in the St. Lucie Estuary.




Figure ES-4. Seven-day moving average of the surface and bottom salinities at the US1 Bridge in the St. Lucie Estuary.




Figure ES-5. Mean oyster recruitment at the Rio oyster monitoring station and 14-day mean salinity at US1 Bridge.




Figure ES-6. Basins, water control structures, and salinity monitoring sites in the Caloosahatchee River Estuary.




Figure ES-7. Total daily inflows from Lake Okeechobee, and runoff from the C-43 and Tidal basins into the Caloosahatchee River Estuary.

Table ES-2. Seven-day mean salinity at six monitoring sites in the Caloosahatchee River Estuary. Current means are in bold font; previous week's means are in parentheses. The envelope in the upper estuary sites is for the protection of tape grass and the envelope in the lower estuary is the optimum salinity range for adult eastern oysters (*Crassostrea virginica*). Data are provisional.

Sampling Site	Surface	Bottom	Optimum Envelope
S-79 (Franklin Lock)	6.2 (7.0)	6.5 (7.2)	0.0 – 10.0
Val I-75	8.1 (7.2)	9.7 (10.5)	0.0 – 10.0
Fort Myers Yacht Basin	17.2 (16.8)	17.7 (20.9)	0.0 – 10.0
Cape Coral	25.0 (23.8)	25.8 (25.7)	10.0 – 25.0
Shell Point	33.7 (32.3)	34.1 (32.8)	10.0 – 25.0
Sanibel	35.8 (34.7)	35.8 (34.7)	10.0 – 25.0




Figure ES-8. Mean daily salinity at upper Caloosahatchee River Estuary monitoring sites and mean daily flow at S-79.




Figure ES-9. Mean daily surface salinity at lower Caloosahatchee River Estuary monitoring sites and mean daily flow at S-79.




Figure ES-10. Seven-day moving average of surface and bottom salinities at Cape Coral, Shell Point, and Sanibel monitoring sites in the Caloosahatchee River Estuary.




Figure ES-11. Mean oyster recruitment at the Iona Cove oyster monitoring station and 14-day mean salinity at Cape Coral.




Figure ES-12. Mean oyster recruitment at the Bird Island oyster monitoring station and 14-day mean salinity at Shell Point.

Table ES-3. Predicted salinity at Val I-75 in the Caloosahatchee River Estuary at the end of the forecast period for various S-79 flow release scenarios.

Scenario	Simulated S-79 Flow (cfs)	Tidal Basin Runoff (cfs)	Daily Salinity	30-Day Mean Salinity
A	450	47	7.7	8.2
B	750	47	6.0	7.5
C	1,000	47	4.4	7.0
D	1,500	47	2.4	6.3
E	2,000	47	1.2	5.8




Figure ES-13. Surface salinity forecast at the Val I-75 site assuming a 450 cfs pulse release at S-79.




Figure ES-14. 30-day moving average flow at S-79 for the Caloosahatchee River Estuary Minimum Flows and Minimum Levels (MFL).




Figure ES-15. Average daily flow (cfs) at Lainhart Dam for the Loxahatchee River Estuary Minimum Flows and Minimum Levels (MFL).




Figure ES-16. 20-day moving average salinity at Lainhart Dam for the Loxahatchee River Estuary Minimum Flows and Minimum Levels (MFL).

Stormwater Treatment Areas

STA-1E: STA-1E Central Flow-way is offline for construction activities. An operational restriction is in place in the Western Flow-way for post-construction vegetation grow-in. Online treatment cells are at or slightly above target stage. The 365-day PLR for the Western and Eastern Flow-way is below 1.0 g/m²/year (**Figure S-2**).

STA-1W: STA-1W Eastern Flow-way is offline for vegetation management activities. Most treatment cells are at target stage. Vegetation in the Western and Eastern Flow-ways is highly stressed. The 365-day PLRs for the Northern and Western Flow-ways are below 1.0 g/m²/year (**Figure S-2**).

STA-2: Operational restrictions are in place in Flow-ways 2, 3 and 4 for vegetation management activities. Treatment cells are at target stage or slightly below target stage. The 365-day PLRs for all Flow-ways are below 1.0 g/m²/year (**Figure S-3**).

STA-3/4: An operational restriction is in place in the Eastern Flow-way for vegetation management activities and the Central Flow-way is off-line for vegetation rehabilitation. Most treatment cells are slightly above target stage. Vegetation in the Central Flow-way is highly stressed. The 365-day PLR for the Eastern, Central, and Western Flow-ways are below 1.0 g/m²/year (**Figure S-3**).

STA-5/6: Treatment cells are predominately at or above target stage with some cells below target stage. All treatment cells have highly stressed vegetation conditions. The 365-day PLRs for all Flow-ways are below 1.0 g/m²/year. (**Figure S-4**).

For definitions on STA operational language see glossary following figures

Everglades Stormwater Treatment Areas - STAs

Estimated Inflow and Outflow Volumes

Feb. 16th, 2026 - Feb 22nd, 2026 *Includes preliminary data*

- Total WY2026 inflows to STAs (5/1/2025 to 2/22/2026): ~581,000 ac-ft
- Lake Okeechobee releases to FEBs/STAs
 - 2/16/2026 to 2/22/2026: 13,600 ac-ft
 - WY2026: ~ 83,200 ac-ft
- Extensive vegetation management activities underway to address stressed and highly stressed vegetation in EAV cells
- All treatment cells are at or near target water depth

	Total Inflow (acre-feet)	Total Outflow (acre-feet)
STA-1E	900	60
STA-1W	900	50
STA-2	3,600	130
STA-3/4	6,400	3,700
STA-5/6	0	0




Figure S-1. STA depths and flow volumes

0 CFS Lake release capacity in Eastern Flow Path:
 2/23/2026 to 3/1/2026
 Subject to change weekly as dry season progresses




Figure S-2. Eastern Flow Path Weekly Status Report

500 CFS Lake release capacity in Central Flow Path:
2/23/2026 to 3/1/2026

- Subject to change weekly as dry season progresses




Figure S-3. Central Flow Path Weekly Status Report




Figure S-4. Western Flow Path Weekly Status Report

Basic Concepts and Definitions for STA Weekly Status Report

- **Inflow:** Sum of flow volume at all inflow structures to an STA.
- **Lake Inflow:** Portion of the STA total inflow volume that originates from Lake Okeechobee.
- **Outflow:** Sum of flow volume at outflow structures from an STA.
- **Total Phosphorus (TP):** Total mass of phosphorus in all its forms; including particulate, dissolved, etc.
- **Inflow Concentration:** TP concentration is the mass of TP in micrograms per liter of water, $\mu\text{g/L}$ or ppb. Inflow concentration refers to the flow-weighted mean TP from all inflow structures over a period of time.
- **Outflow Concentration:** The flow-weighted mean TP from all outflow structures over a period of time. The outflow concentration represents the reduction of inflow TP achieved by STA treatment of the inflow water.
- **WQBEL:** The STA outflow concentration that is required upon completion of the Restoration Strategies projects by December 2025. The outflow concentration shall not exceed 13 ppb as an annual flow weighted mean in more than 3 out of 5 water years on a rolling basis and shall not exceed 19 ppb as an annual flow weighted in any water year.
- **Flow-Way (FW):** One or more treatment cells connected in series. Cells typically have emergent aquatic vegetation (EAV) in the front portion of the flow-way followed by a mix of EAV and submerged aquatic vegetation (SAV)
- **Vegetation Status:** Healthy means the vegetation condition is good and will allow the STA to perform as designed. Stressed means the vegetation is showing signs of poor health, such as browning or areas of vegetation die-off, or the cell contains undesirable vegetation such as floating exotic vegetation requiring treatment. The TP reduction capability of the STA is affected when the vegetation condition is poor.
- **Phosphorus Loading Rate (PLR):** Mass of inflow TP in grams, divided by total treatment area of STA in square meters, per year. In general, a 365-day value of less than 1.0 is needed for an STA to perform optimally. A PLR of 2.0 is considered very high and a PLR of 3.0 is considered extremely high. The TP reduction capability of the STA is affected when the PLR is high, very high and extremely high.
- **Online:** Online status means the FW can receive and treat inflow.
- **Online with Restriction:** The FW can receive and treat inflow, but the amount of flow or water level may be limited temporarily. For example, a vegetation rehabilitation effort may require reduced flows through an area while the new plants are establishing, or nesting by protected species may require a certain water level not to be exceeded.
- **Offline:** The FW is unable to receive and treat inflow due to repairs, construction, or other prohibitive reasons.
- **Depth:** Difference between the average surface water level in a cell and the average ground elevation in that cell. Target depths, or depths between flow events, are between 1.25 ft to 1.5 ft. As depth approaches or drops below zero, an increasing percentage of the cell is considered dry and STA conditions deteriorate. An increase in depth above target depth is expected with increasing flow. However, as depth increases much above the target depth and is sustained over a period of time, it can be detrimental to vegetation health and overall STA treatment performance.
- **Note:** The data provided in this summary report were developed using a combination of provisional and quality-assured flow and water quality data. In some cases, best professional judgment was used to estimate missing data and revise questionable data. Values provided are not considered final but are appropriate for use in STA operational decision-making.

Everglades

Water Conservation Area Regulation Schedules

WCA-1: Stage change at the 1-8C gauge last week remained steady, with stage 0.56 feet below the falling A1 zone regulation line on Monday, February 23, 2026 (**Figure EV-1**).

WCA-2A: Last week's depth change at the 2-17 gauge remained on a steady downward trend, stages were around 1.38 feet above the regulation line on Monday (**Figure EV-2**).

WCA-3A: The 3-gauge average remains well within zone B and falling faster than the slope of the regulation line. On Monday, stages were approximately 1.67 feet below the zone A regulation line. Stage at Gauge 62 (NW corner) continues a steady decline, below the Upper Schedule regulation line by 1.14 feet on Monday (**Figures EV-3 and EV-4**).

Water Depths

The SFWDAT model output for February 23, 2026, illustrates progressive recessions throughout the EPA. Northern WCA-1 is approaching below ground conditions. Southern WCA-2A remains deep for this time of year. Very dry conditions expand across Northern WCA-3A. Depths continue to decline steadily in WCA-3A and -3B and remain very low for this time of year with potential impacts to system-wide ecology. Big Cypress National Preserve is also very low, below surface across much of the park. Northeast Shark River Slough (NESRS) is still hydrated, however, hydrologic connectivity within the major sloughs of Everglades National Park (ENP) has declined. Some standing water may still be present within Taylor Slough. Comparing current conditions to depths over the last twenty years, a majority of Big Cypress, WCA-3A, WCA-3B and ENP remain below the 10th percentiles (as they have for most of the dry season). Southern WCA-2A and 2B depths remain above the 90th percentile. Depths throughout most of WCA-1 have now fallen below the 10th percentile (**Figures EV-5 and EV-6**).

Taylor Slough and Florida Bay

All stages across Taylor Slough decreased over the past week, with an average decrease of 0.09 feet for the week. Changes ranged from -0.13 feet at Taylor Slough Bridge (TSB) and E112, both in the northern slough, to -0.06 feet at EPSW in the C-111 area (**Figure EV-7 and Figure EV-8**). Taylor Slough water levels remain below the recent average (WY1993-2016) for this time of year by 9.5 inches compared to before the Florida Bay Initiative (starting in 2017), a decrease of 0.4 relative to last week. Stage at TSB remains below ground, indicating a lack of water at the head of the slough (**Figure EV-8**). The Craighead Pond (CP) and TSB stages remain below the estimated average for (circa 1900) by 0.88 and 2.82 feet, respectively.

Average Florida Bay salinity was 35.0. Salinity changes ranged from -0.3 at Duck Key (DK) in the eastern region to +1.4 at Garfield Bight (GB) in the western nearshore region (**Figure EV-7**). Salinity is above the estimated historical average (circa 1900) and above the WY2001-2016 Interquartile Range (IQR) 75th percentile in all three regions (**Figure EV-9**). Salinity in the western region is near the hypersalinity threshold. Bay-wide salinity

is above its recent average (WY1993-2016) for this time of year by 6.5, a decrease of 0.5 from last week.

Salinity at the Taylor River (TR) station in the mangrove zone (tracked for the Florida Bay MFL) was 24.1, an increase of 5.2 from last week (**Figure EV-10**). The 365-day moving sum of flow from the five major creeks (McCormick Creek, Taylor River, Mud Creek, Trout Creek, West Highway Creek) was unable to be assessed due to missing data.

Average rainfall across Taylor Slough and Florida Bay was approximately 0.00 inches over the past week, based on the 18 gauges used for this report. Rainfall ranged from 0.00 inches at 16 stations to 0.03 inches at DK in the eastern region (**Figure EV-11**). Wind directions and speeds in Florida Bay ranged from 0.2 mph SE on February 21st to 21.4 mph W on February 22nd (**Figure EV-11**).

The Taylor River, Mud Creek, and West Highway Creek flow stations are currently offline until further notice, so data from all five major creeks are unable to be assessed. Based on the available data from Trout and McCormick Creeks, average daily flow totaled -433 ac-feet, with net negative flows for the week. Total daily creek flow ranged from -995 ac-feet on February 19th to 158 ac-feet on February 22nd (**Figure EV-13**). Average daily flow from Alligator Creek was -74 ac-feet, with net negative flows for the week (**Figure EV-13**).

Implications/considerations for water management.

- Stage recessions decreased last week but would need to slow more (around 0.05 feet per week) or begin to ascend in order to protect the wetland ecology from damaging dry downs expected by the end of the dry season in most regions.
 - WCA-3A and ENP continue to experience unseasonably dry conditions.
 - This will further extend the recent run of four consecutive poor wading bird nesting years into the 2026 nesting season.
 - With La Nina conditions this dry season, conserving water within the WCAs will continue to be ecologically beneficial, especially in regions prone to dry out (e.g. WCA-3A North).
- Shallower conditions are needed in southern WCA-2A to recover ridge and slough habitat. However, holding water high in the north of the system, as further dry conditions are predicted, may prove ecologically beneficial as the Everglades dry down begins to accelerate due to increasing evapotranspiration. Input of water into areas prone to wildfire and peat oxidation should be prioritized once needed.
- Taylor Slough depths are receding more quickly than usual for this time of year. Slough connectivity is now restricted and salinities are above their recent average in Florida Bay.
 - Freshwater input into Taylor Slough and the C-111 basin would help moderate salinities and support recovery of estuarine conditions in Florida Bay.

- With flows from north to south within Shark River Slough now restricted, conserving water within WCA-3A and prioritizing southern deliveries through Taylor Slough may provide greater ecological benefits at the broader ecosystem scale. Conserving water in the WCAs while providing limited freshwater input to the sloughs of ENP will require careful consideration of a balance between the upstream and downstream ecological needs of the system. Individual regional recommendations can be found in **Table EV-2**.

Table EV-2. Previous week’s rainfall and water depth changes in Everglades basins.

Everglades Region	Rainfall (inches)	Stage change (feet)
WCA-1	0.00	-0.07
WCA-2A	0.00	-0.13
WCA-2B	0.00	-0.07
WCA-3A	<0.01	-0.10
WCA-3B	<0.01	-0.14
ENP	<0.01	-0.11




Figure EV-1. WCA-1 stage hydrographs and regulation schedule.




Figure EV-2. WCA-2A stage hydrographs and regulation schedule.




Figure EV-3. WCA-3A stage hydrographs (three-gauge average, 3-69W) and regulation schedule.




Figure EV-4. WCA-3A stage hydrograph (Deer gauge; Site 62) and regulation schedule.




Figure EV-5. Everglades water depths from two months ago (left), one month ago (center) and present (right), based on SFWDAT.




Figure EV-6. Present water depths (February 24, 2026) compared to the day of year relative to average (percentile) over the previous 20 years.




Figure EV-7. Taylor Slough water depths and Florida Bay salinities with changes since a week ago.




Figure EV-8. Taylor Slough water depth time series for Taylor Slough Bridge (TSB; northern slough) and Craighead Pond (CP; southern slough).




Figure EV-9. Eastern (top panel), Central (middle panel) and Western (bottom panel) Florida Bay daily average salinities with WY2001-2016 interquartile (25-75 percentile) ranges (IQR) and estimated historical daily average salinities. The hypersalinity threshold indicates the level at which salinities start to become harmful to seagrass.




Figure EV-10. Daily average salinity at Taylor River (TR) tracked for the Florida Bay MFL criteria. The 365-day total creek flow MFL metric is not currently available due to missing creek flow data.




Figure EV-11. Daily average rain across Taylor Slough and Florida Bay, along with hourly average wind speed and direction (measured at Long Key) in Florida Bay over the past four weeks.




Figure EV-12. Top: daily average creek flow summed between the five major creeks with estimated historical daily flow over the past four weeks (**note:** data from Taylor River, Mud Creek and West Highway Creek are currently unavailable since November 21st, 2025). Bottom: Daily average Alligator Creek flow data. N/A indicates missing data.

Table EV-2. Weekly water depth changes and water management recommendations

SFWMD Everglades Ecological Recommendations, February 24, 2026 (red is new)			
	Weekly change	Recommendation	Reasons
WCA-1	Stage decreased by 0.07 feet.	A recession of no faster than 0.05 feet per week.	Conserve water, maintain within basin and downstream habitat and wildlife. Maintain maintenance access for vegetation management.
WCA-2A	Stage decreased by 0.13 feet	A recession of no faster than 0.05 feet per week.	Maintain within basin (north versus south) and downstream habitat and wildlife.
WCA-2B	Stage decreased by 0.07 feet	A recession of no faster than 0.12 feet per week.	Protect within basin and downstream habitat and wildlife.
WCA-3A NE	Stage decreased by 0.10 feet	A recession of no faster than 0.05 feet per week.	Conserve water, maintain within basin and downstream habitat and wildlife. Provide suitable depths for aquatic prey and protect against peat soil loss during the dry season.
WCA-3A NW	Stage decreased by 0.08 feet	A recession of no faster than 0.05 feet per week.	
Central WCA-3A S	Stage decreased by 0.12 feet	A recession of no faster than 0.05 feet per week.	Conserve water, maintain within basin and downstream habitat and wildlife. Provide suitable depths for aquatic prey and protect against peat soil loss during the dry season.
Southern WCA-3A S	Stage decreased by 0.10 feet		
WCA-3B	Stage decreased by 0.14 feet	A recession of no faster than 0.12 feet per week.	Protect within basin and downstream habitat and wildlife.
ENP-SRS	Stage decreased by 0.11 feet.	Make discharges to ENP according to COP protocol, considering up/down stream ecological conditions.	Protect within basin and upstream habitat and wildlife.
Taylor Slough	Stage changes ranged from -0.13 feet to -0.06 feet	Move water southward as possible.	When available, provide freshwater to promote water movement.
FB- Salinity	Salinity changes ranged from -0.3 to +1.4	Move water southward as possible.	When available, provide freshwater to promote water movement.