

Disclaimer: Information contained in the report addresses environmental conditions only and is not the official South Florida Water Management District operations recommendation or decision.

M E M O R A N D U M

TO: John Mitnik, Assistant Executive Director, Executive Office Staff

FROM: SFWMD Staff Environmental Advisory Team

DATE: August 26, 2026

SUBJECT: Weekly Environmental Conditions for Systems Operations

Summary

Weather Conditions and Forecast

Moisture levels will continue to increase across South Florida as the northern extent of a tropical wave approaches the region. Meanwhile, the subtropical ridge will continue rebuilding westward across Florida as the upper-level trough over the northeastern United States lifts farther away. This pattern has allowed the steering currents to become southeasterly along the lower east coast while remaining more southwesterly north of Lake Okeechobee.

By Wednesday, tropical moisture associated with the tropical wave will overspread the region. The increase in moisture should result in a more active rainfall pattern, with scattered to numerous showers and thunderstorms expected across much of the SFWMD. The southeasterly steering currents will also favor periods of morning shower activity along portions of the east coast and Florida Keys, followed by more widespread thunderstorm development across the interior during the afternoon.

By Thursday and Friday, the subtropical ridge is forecast to nudge farther westward across Florida, allowing the steering currents to become southeasterly to south southeasterly across most of the region. This pattern should favor inland propagation of both the Atlantic and Gulf Seabreeze boundaries. With the steering flow oriented generally parallel to the peninsula, the two boundaries may collide over the central interior during the late afternoon, favoring stronger thunderstorms and locally heavy rainfall.

By the weekend, the subtropical ridge is forecast to become more established across Florida, causing the steering currents to veer more easterly to southeasterly across South Florida. This pattern may also draw another surge of tropical moisture into the region as an additional tropical wave approaches from the east. The active rainfall pattern should therefore persist, with morning showers along portions of the east coast followed by scattered to numerous afternoon thunderstorms. As the steering flow becomes more easterly, the greatest concentration of heavy afternoon rainfall should shift toward the western interior and southwest coast, where greater convergence is expected along the Gulf Sea breeze. For the 7-day period ending next Tuesday morning, near- to above-average total SFWMD rainfall is possible.

Kissimmee

The water level is being allowed to rise as rainfall permits in East Lake Toho and is at the regulation schedule line in Lake Toho. Releases from Lakes Kissimmee-Cypress-Hatchineha followed the Headwaters Revitalization Schedule Increment 1 Temporary Deviation Discharge Plan. Weekly average discharge on August 23, 2026, was 150 cfs at S-65 and 150 cfs at S-65A. Mean weekly water depth on the Kissimmee River floodplain was unchanged at 0.33 feet. The weekly average concentration of dissolved oxygen in the Kissimmee River decreased from 5.7 mg/L the previous week to 4.6 mg/L, which is above both the potentially lethal level of 1.0 mg/L and the stressful level of 2.0 mg/L for Florida bass and other species.

Lake Okeechobee

Lake Okeechobee stage was 9.56 feet NAVD88 (10.87 ft NGVD29) on August 23, 2026, which was 0.11 feet lower than the previous week and 0.03 feet higher than a month ago. The lake remains in the water shortage management band. Average daily inflows (excluding rainfall) decreased from 780 cfs the previous week to 390 cfs. Average daily outflows (excluding evapotranspiration) increased from 80 cfs the previous week to 540 cfs. The August 23, 2026, satellite image from NOAA's Harmful Algal Bloom Monitoring System suggests moderate to high cyanobacteria potential along most of the shallow nearshore regions.

Estuaries

Total inflow to the St. Lucie Estuary averaged 517 cfs over the past week with no flow coming from Lake Okeechobee. Salinities increased at the HR1 and US1 Bridge sites and decreased at the A1A Bridge site. Salinity in the middle estuary was in the optimal range (10–25) for adult eastern oysters.

Total inflow to the Caloosahatchee River Estuary averaged 1,594 cfs over the past week with 177 cfs coming from Lake Okeechobee. Over the past week, salinities decreased at all sites in the estuary. Salinities were in the optimal range (0-10) for tape grass at all sites in the upper estuary. Salinities were in the optimal range (10-25) for adult eastern oysters at Cape Coral, and in the upper stressed range (>25) at Shell Point and Sanibel.

Stormwater Treatment Areas

For the week ending Sunday, August 23rd, 2026, no Lake Okeechobee water was delivered to the FEBs/STAs. The total amount of Lake releases sent to the FEBs/STAs in WY2027 is approximately 9,000 ac-feet. The total amount of inflows to the STAs in WY2027 is approximately 87,000 ac-feet. Most online STA treatment cells are at or near target stage. STA-1E Central Flow-way is offline for post-construction vegetation grow-in. STA-1W Eastern Flow-way is offline for vegetation management activities. Operational restrictions are in effect in STA-1E Western Flow-way, STA-2 Flow-way 2, and STA-3/4 Eastern Flow-way for vegetation management activities. This week, if LOSOM recommends Lake releases to the WCAs and conditions allow, releases will be sent to STA-2 and STA-3/4.

Everglades

Rainfall over the last week was below average in Everglades Protection Area (EPA) and much below average in the northern WCAs. Stage changes across the EPA reflected the rainfall patterns with recessions occurring in WCA-1 and WCA-2A, and slight ascensions or relatively stable water depth changes to the south. Heavy localized rainfall increased stages in some areas. Water depths across portions of central and southern WCA-3A have improved compared to last month but remain very shallow for this time of year. All basins of the EPA are within the 10th – 20th percentile and persistently low in northeastern WCA-3A, where satellite monitoring is showing very dry soils. These dry conditions can have ecological consequences system wide, including reduced prey production, increased risk of damaging wildfires, enhanced peat oxidation, and potential ridge and slough degradation. Everglades National Park (ENP) is currently experiencing significant wildfire activity generally focused to the south and west. Taylor Slough stages decreased last week remaining well below the recent average for this time of year. Average Florida Bay salinity decreased slightly last week, but the central and western regions of Florida Bay remain above the hypersalinity threshold with the eastern region now at the threshold. Bay-wide salinities are above their recent average by 13.5. Based on previous studies and surveys, high temperatures and hypersalinity in the central regions of FL Bay may initiate a seagrass die-off if upstream flows into the bay and direct rainfall are less than 50% of normal.

Supporting Information

Kissimmee Basin

Upper Kissimmee

On August 23, 2026, mean daily lake stages were 55.0 feet NAVD88 (0.5 feet below schedule) in East Lake Toho, 52.5 feet NAVD88 (at schedule) in Lake Toho, and 47.6 feet NAVD88 (2.7 feet below the Increment 1 Temporary Deviation schedule) in Lakes Kissimmee-Cypress-Hatchineha (KCH) (**Table KB-1, Figures KB-1-3**).

Lower Kissimmee

For the week ending August 23, 2026, mean weekly discharge was 150 cfs at S-65 and 150 cfs at S-65A. Mean weekly discharge from the Kissimmee River was 350 cfs at S-65D and 210 cfs at S-65E (**Table KB-2**). Mean weekly headwater stages were 45.2 feet NAVD88 at S-65A and 27.5 feet NAVD88 at S-65D. Mean weekly river channel stage decreased by 0.1 to 29.7 feet NAVD88 (**Figure KB-4**). Mean weekly water depth on the Kissimmee River floodplain was unchanged at 0.33 feet (**Table KB-2, Figure KB-5**). The weekly average concentration of dissolved oxygen in the Kissimmee River decreased from 5.7 mg/L the previous week to 4.6 mg/L (**Table KB-2, Figure KB-6**).

Water Management Recommendations

Allow stage in East Lake Toho and Lake Toho to rise with rainfall and, to the extent possible, limit the ascension rate to no more than 0.5 ft/14 days. In KCH, follow the Headwaters Revitalization Schedule (HRS) Increment 1 Temporary Deviation Discharge Plan for S-65/S-65A (**Figure KB-7**). With KCH stage in Zone B5, target flows of 150 cfs; if stage increases into Zone B4, target flows of 300 cfs.

Table KB-1. Average discharge for the preceding seven days, Sunday's average daily stage and Sunday's average daily departure from Kissimmee Chain of Lakes (KCOL) flood regulation lines or temporary schedules. All data are provisional.

Water Body	Structure	Stage Monitoring Site	Weekly (7-Day) Average Discharge (cfs)	Sunday Lake Stage (feet NAVD88) ^a	Schedule Type ^b	Sunday Schedule Stage (feet NAVD88)	Sunday Departure from Regulation (feet)	
							8/23/26	8/16/26
Lakes Hart and Mary Jane	S-62	LKMJ	0	59.0	R	59.0	0.0	0.1
Lakes Myrtle, Preston and Joel	S-57	S-57	0	58.9	R	59.9	-1.0	-1.0
Alligator Chain	S-60	ALLI	0	60.9	R	62.1	-1.2	-1.1
Lake Gentry	S-63	LKGT	0	59.1	R	59.9	-0.8	-0.8
East Lake Toho	S-59	TOHOE	0	55.0	R	55.5	-0.5	-0.6
Lake Toho	S-61	TOHOW S-61	0	52.5	R	52.5	0.0	0.0
Lakes Kissimmee, Cypress and Hatchineha	S-65	KUB011 LKIS5B	150	47.6	T	50.3	-2.7	-2.6

a. Names of in-lake monitoring sites and structures used to determine lake stage. If more than one site is listed, an average is reported.

b. A: projected recession line; R: USACE regulation schedule; S: temporary recession target line; T: temporary schedule; NA: not applicable or not available.




Figure KB-1. East Lake Toho regulation schedule, stage, discharge, and rainfall.




Figure KB-2. Lake Toho regulation schedule, stage, discharge, and rainfall.




Figure KB-3. Lakes Kissimmee, Cypress and Hatchineha regulation schedule, stage, discharge, and rainfall.

Table KB-2. One- and seven-day average discharge and stage at Lower Kissimmee basin structures, river channel dissolved oxygen concentrations and water depths in the Phase I area floodplain. All data are provisional.

Metric	Location	Sunday Daily Average	Weekly Average for Previous Seven Day Periods			
		8/23/26	8/23/26	8/16/26	8/9/26	8/2/26
Discharge	S-65	150	150	120	140	140
Discharge	S-65A ^a	150	150	150	140	140
Headwater Stage (feet NAVD88)	S-65A	45.2	45.2	45.2	45.3	45.2
Discharge	S-65D ^b	N/A	350	380	360	270
Headwater Stage (feet NAVD88)	S-65D ^c	24.6	27.5	27.5	27.5	27.5
Discharge (cfs)	S-65E ^d	130	210	260	250	180
Discharge (cfs)	S-67	0	0	0	0	0
Dissolved Oxygen (mg/L) ^e	Phase I, II/III river channel	4.7	4.6	5.7	5.4	6.2
River channel mean stage (feet NAVD88) ^f	Phase I river channel	29.7	29.7	29.8	29.8	29.7
Mean depth (feet) ^g	Phase I & II/III floodplain	0.33	0.33	0.33	0.33	0.33

a. Combined discharge from main and auxiliary structures.

b. Combined discharge from S-65D, S-65DX1, and S-65DX2.

c. Average stage from S-65D and S-65DX1.


d. Combined discharge from S-65E and S-65EX1.

e. Dissolved oxygen is the average of values from sondes KRBN, PC62, PC33, PD62R, and PD42R.

f. Mean of five river channel stations (PC62, KRDR02, KRBN, PC33, PC11) in the Phase I area.

g. One-day spatial average obtained from the South Florida Water Depth Assessment Tool (SFWDAT).

Stage and Discharge Hydrograph (report date: 8/25/2026; data through: 8/23/2026)



*River Channel Stage is the average for PC62, KRDR02, KRBN, PC33, and PC11.

sfwmd.gov

Figure KB-4. Kissimmee River stage, discharge, and rainfall.





Figure KB-5. Phase I-II-III area Kissimmee River floodplain water depths (from left to right) one year ago, one month ago, and current.



Report Date: 8/25/2026; data are through: 8/23/2026

sfwmd.gov

Figure KB-6. Kissimmee River channel mean daily dissolved oxygen concentration (mg/L), S-65A discharge (cfs), temperature (°C) and rainfall (inches). Dissolved oxygen (DO) and temperature are mean daily values averaged for PC62, KRDR02, KRBN, PC33, PC11, PD62R, and PD42R with an average of five stations reporting this week. Rainfall values are daily totals for Kissimmee River (Pool BCD) AHED watershed.


SOUTH FLORIDA WATER MANAGEMENT DISTRICT

HRS Increment 1 Temporary Deviation Discharge Plan for S-65/S-65A

Discharge Guidance for Increment 1 Temporary Deviation Discharge Plan		
ZONE	S-65 RELEASES	S-65A TARGET FLOWS
ZONE A	Releases for Flood Risk Management up to maximum structure capacity as determined by downstream constraints with a firm capacity of 3,000 cfs.	
ZONE B1	1,400 cfs minimum ramp to 3,000 cfs at Zone A boundary	S-65A releases between 1,400 cfs and 3,000 cfs at Zone A boundary based on Table 1
ZONE B2	Releases as needed to target flows at S-65A	Target S-65A flows of 1,400 cfs to meet ecological needs
ZONE B3	Releases as needed to target flows at S-65A	S-65A flows between 300 cfs and 1,400 cfs
ZONE B4	Releases as needed to target flows at S-65A	Target S-65A flows of 300 cfs
ZONE B5	Releases as needed to target flows at S-65A	Target S-65A flows of 150 cfs
ZONE C	0 cfs	Flow as needed to maintain optimum S-65A headwater

Table KB-3. Maximum Rate of Change Limits for S-65A		
MAXIMUM Release Rate of Change Limits for S-65A. In general recommended rates of change will be slower than shown in this table.		
Q (cfs)	Maximum rate of INCREASE (cfs/day)	Maximum rate of DECREASE (cfs/day)
0-300	50	-50
301-650	75	-75
651-1400	150	-150
1401-3000	300	-600
>3000	1000	-2000

sfwmd.gov



Other Considerations

- When possible, limit lake ascension rate in the Jun 1 - Aug 15 window to 0.25 ft per 7 days in Lakes Kissimmee, Cypress, Hatchineha (S-65), East Toho (S-59) and Toho (S-61).
- If outlook is for extreme dry conditions meet with KB staff to discuss modifications to this plan.

Slide Revised 7/29/2024

Figure KB-7. Headwaters Revitalization Schedule (HRS) Increment 1 Temporary Deviation Discharge Plan for S-65/S-65A.

Lake Okeechobee

Lake Okeechobee stage was 9.56 feet NAVD88 (10.87 ft NGVD29) on August 23, 2026, which was 0.11 feet lower than the previous week and 0.03 feet higher than a month ago (**Figure LO-1**). Lake stage remains in the water shortage management band (1.34 feet below the upper limit, **Figure LO-2**) and is 1.26 feet below the ecological envelope (**Figure LO-3**). According to NEXRAD, 0.94 inches (approximately 35,000 acre-feet) of rain fell directly over the Lake during the previous week, and 1.31 inches (approximately 36,900 acre-feet) were lost to evapotranspiration.

Average daily inflows (excluding rainfall) decreased from 780 cfs the previous week to 390 cfs. The largest inflow came from the Kissimmee River (210 cfs via S-65E(X1)). Average daily outflows (excluding evapotranspiration) increased from 80 cfs the previous week to 540 cfs. The largest outflow was to the west into the C-44 canal (370 cfs via S-77). **Figures LO-4 and LO-5** show the combined average daily inflows and outflows for the Lake over the past eight weeks, and the average inflows and outflows last week, respectively.

In the most recent non-obscured satellite image from August 23, 2026, NOAA's Harmful Algal Bloom Monitoring System suggests moderate to high cyanobacteria potential along most of the shallow nearshore regions (**Figure LO-6**).

The routine water quality and phytoplankton monitoring sampling trips are now on the bloom season (May-Oct) twice per month sampling schedule. Provisional phytoplankton results from the August 3 - 5 sampling event showed 14 of the 27 phytoplankton samples collected had detectable levels of cyanotoxins; six samples had detectable cylindrospermopsin and eight had detectable microcystins (**Figure LO-7**). Only 18 of the 27 water quality samples had valid chlorophyll *a* results, of those, two had values > 40 µg/L, indicating bloom level concentrations, while 11 samples had values between 20 and 40 µg/L (**Figure LO-7**).

Note: All data presented in this report are provisional and are subject to change.




Figure LO-1. Lake Okeechobee water depth estimates based on South Florida Water Depth Assessment Tool (SFWDAT).




Figure LO-2. Recent Lake Okeechobee stages with projected stages based on a conditional position analysis.
 Note: stages are in NGVD29, approximate NAVD88 values are shown for reference.




Figure LO-3. The current and select prior year's annual lake stage hydrographs in comparison to the Lake Okeechobee ecological envelope (light grey).




Figure LO-4. Major inflows (orange) to and outflows east and west (blue) from Lake Okeechobee. Outflows south are shown in green. Flows into Lake Okeechobee from the L-8 canal through S-271 (formerly Culvert 10A) or from the C-44 canal through the S-308 are included as inflows. Conversely, flows from Lake Okeechobee into the L-8 or C-44 canals are included with outflows. Inflows are shown as positive values; outflows are negative. Outflows through the S-77 (Caloosahatchee) and S-308 (C-44 Canal) structures are based on downstream gauges to include flows to lock openings for navigation.




Figure LO-5. Inflows into Lake Okeechobee from Indian Prairie basins, Taylor Creek/Nubbin Slough, Kissimmee River and Fisheating Creek (currently no flow data available for FECR), and outflows to the west via S-77, to the east via S-308, to the south via S-351, S-352, S-354, and to southeast via S-271 (formerly Culvert 10A) for the week of August 17 - 23, 2026.




Figure LO-6. Cyanobacteria bloom index level on Lake Okeechobee, based on NOAA's harmful algal bloom monitoring system. Gray color indicates cloud cover. *Provisional NOAA image, subject to change*.

Collection Date: August 3-5, 2026

Station	CHL _a (ug/L)	TOXIN (ug/L)	TAXA	Station	CHL _a (ug/L)	TOXIN (ug/L)	TAXA
FEBIN				L001	29.6	0.1	Microcys
FEBOUT	22.6	BDL	Raphi/Plank	L004	33.3	1.6	Microcys
KISSR0.0	36.0	BDL	mixed	L006		0.3	Micro/Dinop
L005	7.4	BDL	mixed	L007		BDL	mixed
LZ2	27.2	BDL	mixed	L008	36.4	0.3	Microcys
KBARSE	15.1	0.2	Plank/Botry	LZ30		0.3	Microcys
RITTAE2				LZ40		0.7	Microcys
PELBAY3				CLV10A		0.1	Microcys
POLE3S				NCENTER	39.3	0.2	Planktol
LZ25A							
PALMOUT		BDL	Microcys	S308C	19.2	0.5	Microcys
PALMOUT1		BDL	Microcys	S77	51.4	BDL	mixed
PALMOUT2		0.5	mixed	> SFWMD considers >40µg/L Chlorophyll _a an algal bloom > BDL – Below Detectable Limit of 0.2 µg/L (Cyl = 0.1 µg/L) > ND – No Dominant taxa > F – Flagged Sample > Blank – Not sampled > Station bold font – crew observed possible BGA > Chlorophyll <i>a</i> (CHL _a) analyzed by SFWMD > Toxin & Taxa analyzed by FDEP: <i>Microcys</i> = <i>Microcystis</i> ; <i>Raphi</i> = <i>Raphidiopsis</i> ; <i>Planktol</i> = <i>Planktolyngbya</i> ; <i>Dolicho</i> = <i>Dolichospermum</i> ; <i>Botry</i> = <i>Botryococcus</i> ; <i>Dinop</i> = <i>Dinophyceae</i> Toxins include cylindrospermopsin* and/or microcystins			
PALMOUT3		0.3	mixed				
POLESOUT	23.9	BDL	Raphi/Plank				
POLESOUT1	16.9	BDL	Dolic/Plank				
POLESOUT2	18.2	BDL	Microcys				
POLESOUT3	25.4	BDL	Microcys				
EASTSHORE	30.9	0.1	Microcys				
NES135	68.2	0.1	Microcys				
NES191	22.7	BDL	mixed				




Figure LO-7. Dominant taxa, cyanotoxins (µg/L) and chlorophyll *a* (µg/L) concentration data from August 3-5, 2026. Sampling locations, chlorophyll *a*, and total toxin concentrations are overlaid on the August 7, 2026 image from NOAA’s harmful algal bloom monitoring system. Gray color indicates cloud cover.

Estuaries

St. Lucie Estuary

Over the past week, mean total inflow to the St. Lucie Estuary was 517 cfs (**Figures ES-1 and ES-2**), and the previous 30-day mean inflow was 622 cfs. For comparison, the historical provisional mean inflows from contributing areas are shown in **Figure ES-2**.

Over the past week, salinities increased at the HR1 and US1 Bridge sites and decreased at the A1A Bridge site (**Table ES-1 and Figure ES-3**). The seven-day moving average water column salinity at the US1 Bridge was 20.1. Salinity conditions in the middle estuary were estimated to be within the optimal range for adult eastern oysters (**Figure ES-4**). The mean larval oyster recruitment rate reported by the Fish and Wildlife Research Institute (FWRI) for July was 7.8 spat/shell at Rio, which is an increase from the previous month (**Figure ES-5**).

Caloosahatchee River Estuary

Over the past week, mean total inflow to the Caloosahatchee River Estuary was 1,594 cfs (**Figures ES-6 and ES-7**), and the previous 30-day mean inflow was 2,113 cfs. For comparison, the historical provisional mean inflows from the contributing areas are shown in **Figure ES-7**.

Over the past week, salinities decreased at all sites in the estuary (**Table ES-2 and Figures ES-8 and ES-9**). The seven-day mean water column salinity (**Table ES-2**) was in the optimal range (0–10) for tape grass in the upper estuary. The seven-day mean salinity values were within the optimal range for adult eastern oysters at Cape Coral, and in the upper stressed range at Shell Point and Sanibel (**Figure ES-10**). The mean larval oyster recruitment rates reported by the FWRI in July were 3.4 spat/shell at Iona Cove and 7.1 spat/shell at Bird Island, which is a decrease at Iona Cove and an increase at Bird Island compared to the previous month (**Figures ES-11 and ES-12**).

Surface salinity at Val I-75 was forecast for the next two weeks using an autoregression model (Qiu and Wan, 2013¹) coupled with a linear reservoir model for the tidal basin. Model scenarios included pulse releases at S-79 ranging from 450 to 2,000 cfs, with estimated tidal basin inflows of 444 cfs. Model results from all scenarios predict daily salinity to be 5.6 or lower and the 30-day moving average surface salinity to be 3.5 or lower at Val I-75 at the end of the two-week period (**Table ES-3 and Figure ES-13**). This keeps predicted salinities in the upper estuary within the optimal salinity range (0–10) for tape grass.

¹ Qiu, C., and Y. Wan. 2013. Time series modeling and prediction of salinity in the Caloosahatchee River Estuary. *Water Resources Research* 49:5804-5816.

Red Tide

The FWRI reported on August 21, 2026, that *Karenia brevis*, the Florida red tide dinoflagellate, was not observed in any samples collected within the District region.

Water Management Recommendations

Lake stage is in the Water Shortage Management Zone. Current climatological and hydrological conditions are normal. The LOSOM release guidance suggests no release at S-79 to the Caloosahatchee River Estuary and no releases at S-80 to the St. Lucie Estuary.




Figure ES-1. Basins, water control structures and salinity monitoring sites in the St. Lucie Estuary.




Figure ES-2. Total daily inflows from Lake Okeechobee and runoff from the C-44, C-23, C-24, Ten Mile Creek, and Tidal Basins into the St. Lucie Estuary.

Table ES-1. Seven-day mean salinity at oyster monitoring sites in the St. Lucie Estuary. Current means are in bold font; previous week's means are in parentheses. The envelope reflects the optimum salinity range for adult eastern oysters (*Crassostrea virginica*) in the estuary. Data are provisional.

Sampling Site	Surface	Bottom	Optimum Envelope
HR1 (North Fork)	13.3 (12.6)	18.7 (17.9)	10.0 – 25.0
US1 Bridge	19.6 (19.3)	20.6 (20.1)	10.0 – 25.0
A1A Bridge	26.6 (27.3)	29.1 (29.4)	10.0 – 25.0




Figure ES-3. Mean daily salinity at the A1A, US1, and HR1 sites in the St. Lucie Estuary.




Figure ES-4. Seven-day moving average of the surface and bottom salinities at the US1 Bridge in the St. Lucie Estuary.




Figure ES-5. Mean oyster recruitment at the Rio oyster monitoring station and 14-day mean salinity at US1 Bridge.




Figure ES-6. Basins, water control structures, and salinity monitoring sites in the Caloosahatchee River Estuary.




Figure ES-7. Total daily inflows from Lake Okeechobee, and runoff from the C-43 and Tidal basins into the Caloosahatchee River Estuary.

Table ES-2. Seven-day mean salinity at six monitoring sites in the Caloosahatchee River Estuary. Current means are in bold font; previous week's means are in parentheses. The envelope in the upper estuary sites is for the protection of tape grass and the envelope in the lower estuary is the optimum salinity range for adult eastern oysters (*Crassostrea virginica*). Data are provisional.

Sampling Site	Surface	Bottom	Optimum Envelope
S-79 (Franklin Lock)	1.4 (1.6)	1.5 (1.7)	0.0 – 10.0
Val I-75	2.0 (2.2)	2.6 (3.7)	0.0 – 10.0
Fort Myers Yacht Basin	7.5 (8.4)	9.4 (10.3)	0.0 – 10.0
Cape Coral	14.3 (15.2)	16.4 (17.0)	10.0 – 25.0
Shell Point	28.7 (30.5)	28.8 (30.5)	10.0 – 25.0
Sanibel	31.7 (33.6)	36.8 (38.0)	10.0 – 25.0




Figure ES-8. Mean daily salinity at upper Caloosahatchee River Estuary monitoring sites and mean daily flow at S-79.




Figure ES-9. Mean daily surface salinity at lower Caloosahatchee River Estuary monitoring sites and mean daily flow at S-79.




Figure ES-10. Seven-day moving average of surface and bottom salinities at Cape Coral, Shell Point, and Sanibel monitoring sites in the Caloosahatchee River Estuary.




Figure ES-11. Mean oyster recruitment at the Iona Cove oyster monitoring station and 14-day mean salinity at Cape Coral.




Figure ES-12. Mean oyster recruitment at the Bird Island oyster monitoring station and 14-day mean salinity at Shell Point.

Table ES-3. Predicted salinity at Val I-75 in the Caloosahatchee River Estuary at the end of the forecast period for various S-79 flow release scenarios.

Scenario	Simulated S-79 Flow (cfs)	Tidal Basin Runoff (cfs)	Daily Salinity	30-Day Mean Salinity
A	450	444	5.6	3.5
B	750	444	3.6	3.0
C	1,000	444	2.8	2.6
D	1,500	444	1.5	2.1
E	2,000	444	0.6	1.8




Figure ES-13. Surface salinity forecast at the Val I-75 site assuming a 450 cfs pulse release at S-79.

Stormwater Treatment Areas

STA-1E: STA-1E Central Flow-way is offline for construction activities. An operational restriction is in place in the Western Flow-way for post-construction vegetation grow-in. Online treatment cells are at or near target stage. The 365-day PLRs for the Western and Eastern Flow-way are below 1.0 g/m²/year (**Figure S-2**).

STA-1W: STA-1W Eastern Flow-way is offline for vegetation management activities. Treatment cells are at or near target stage. Vegetation in the Western and Eastern Flow-ways is highly stressed. The 365-day PLRs for the Northern and Western Flow-ways are below 1.0 g/m²/year (**Figure S-2**).

STA-2: Treatment cells are at or near target stage. An operational restriction is in place in Flow-way 2 for vegetation management activities. The 365-day PLRs for all Flow-ways are below 1.0 g/m²/year (**Figure S-3**).

STA-3/4: An operational restriction is in place in the Eastern Flow-way for vegetation management activities. Most treatment cells are at or near target stage. Vegetation in the Central Flow-way is highly stressed. The 365-day PLRs for the Eastern, Central, and Western Flow-ways are below 1.0 g/m²/year (**Figure S-3**).

STA-5/6: Treatment cells are at or below target stage. All treatment cells have highly stressed vegetation conditions. The 365-day PLRs for all Flow-ways are below 1.0 g/m²/year (**Figure S-4**).

For definitions on STA operational language see glossary following figures.

Everglades Stormwater Treatment Areas - STAs

- Total WY2027 inflows to STAs (5/1/2026 to 8/23/2026): ~87,000 ac-ft
- Lake Okeechobee releases to FEBs/STAs
 - 8/17/2026 to 8/23/2026: 0 ac-ft
 - WY 2027: ~ 9,000 ac-ft
- Extensive vegetation management activities underway to address stressed and highly stressed vegetation in EAV cells
- All treatment cells are at or near target water depth

Estimated Inflow and Outflow Volumes

Aug. 17th, 2026 - Aug. 23rd, 2026 *Includes preliminary data*

	Total Inflow (acre-feet)	Total Outflow (acre-feet)
STA-1E	0	60
STA-1W	0	250
STA-2	0	850
STA-3/4	2,500	4,900
STA-5/6	550	0

Water Depths (8/23/2026)




Figure S-1. STA depths and flow volumes

0 CFS Lake release capacity in Eastern Flow Path:
8/24/2026 to 8/30/2026
Subject to change weekly as wet season progresses




Figure S-2. Eastern Flow Path Weekly Status Report

700 CFS Lake release capacity in Central Flow Path:
8/24/2026 to 8/30/2026
Subject to change weekly as wet season progresses




Figure S-3. Central Flow Path Weekly Status Report

0 CFS Lake release capacity in Western Flow Path:
8/24/2026 to 8/30/2026




Figure S-4. Western Flow Path Weekly Status Report

Basic Concepts and Definitions for STA Weekly Status Report

- **Inflow:** Sum of flow volume at all inflow structures to an STA.
- **Lake Inflow:** Portion of the STA total inflow volume that originates from Lake Okeechobee.
- **Outflow:** Sum of flow volume at outflow structures from an STA.
- **Total Phosphorus (TP):** Total mass of phosphorus in all its forms; including particulate, dissolved, etc.
- **Inflow Concentration:** TP concentration is the mass of TP in micrograms per liter of water, $\mu\text{g/L}$ or ppb. Inflow concentration refers to the flow-weighted mean TP from all inflow structures over a period of time.
- **Outflow Concentration:** The flow-weighted mean TP from all outflow structures over a period of time. The outflow concentration represents the reduction of inflow TP achieved by STA treatment of the inflow water.
- **WQBEL:** The STA outflow concentration that is required upon completion of the Restoration Strategies projects by December 2025. The outflow concentration shall not exceed 13 ppb as an annual flow weighted mean in more than 3 out of 5 water years on a rolling basis and shall not exceed 19 ppb as an annual flow weighted in any water year.
- **Flow-Way (FW):** One or more treatment cells connected in series. Cells typically have emergent aquatic vegetation (EAV) in the front portion of the flow-way followed by a mix of EAV and submerged aquatic vegetation (SAV)
- **Vegetation Status:** Healthy means the vegetation condition is good and will allow the STA to perform as designed. Stressed means the vegetation is showing signs of poor health, such as browning or areas of vegetation die-off, or the cell contains undesirable vegetation such as floating exotic vegetation requiring treatment. The TP reduction capability of the STA is affected when the vegetation condition is poor.
- **Phosphorus Loading Rate (PLR):** Mass of inflow TP in grams, divided by total treatment area of STA in square meters, per year. In general, a 365-day value of less than 1.0 is needed for an STA to perform optimally. A PLR of 2.0 is considered very high and a PLR of 3.0 is considered extremely high. The TP reduction capability of the STA is affected when the PLR is high, very high and extremely high.
- **Online:** Online status means the FW can receive and treat inflow.
- **Online with Restriction:** The FW can receive and treat inflow, but the amount of flow or water level may be limited temporarily. For example, a vegetation rehabilitation effort may require reduced flows through an area while the new plants are establishing, or nesting by protected species may require a certain water level not to be exceeded.
- **Offline:** The FW is unable to receive and treat inflow due to repairs, construction, or other prohibitive reasons.
- **Depth:** Difference between the average surface water level in a cell and the average ground elevation in that cell. Target depths, or depths between flow events, are between 1.25 ft to 1.5 ft. As depth approaches or drops below zero, an increasing percentage of the cell is considered dry and STA conditions deteriorate. An increase in depth above target depth is expected with increasing flow. However, as depth increases much above the target depth and is sustained over a period of time, it can be detrimental to vegetation health and overall STA treatment performance.
- **Note:** The data provided in this summary report were developed using a combination of provisional and quality-assured flow and water quality data. In some cases, best professional judgment was used to estimate missing data and revise questionable data. Values provided are not considered final but are appropriate for use in STA operational decision-making.

Everglades

Water Conservation Areas

Regulation Schedules

WCA-1: Stage fell at the 1-8C gauge last week and was below the A-1 regulation line by 0.95 feet on Sunday, August 23, 2026 (**Figure EV-1**).

WCA-2A: Water depth at the 2-17 gauge fell over last week. Stage was 0.3 feet below the regulation line on Sunday (**Figure EV-2**).

WCA-3A: The 3-gauge average stage remains well within Zone B, remaining steady with a slight incline over the week. On Sunday, stages were around 1.4 feet below the Zone A regulation line. Stage at Gauge 62 (NW corner) fell slightly last week and was below the Upper Schedule line by 0.76 feet on Monday (**Figures EV-3 and EV-4**).

Water Depths

The SFWDAT model output for August 23, 2026, illustrates a drying trend over the last month in WCA-1. Depths in WCA-2A over the last two months remain between 0.5 feet and 1.0 feet, which is low for this time of year. Water levels are increasing across southern and central WCA-3A but remain low in the northeast and along the eastern boundary. Satellite imagery is detecting very dry soil in that region, suggesting the potential for damaging peat fires if dry conditions persist. The Big Cypress basin is also showing a stable to wetting trend although there are issues with the WDAT output in this region. Everglades National Park (ENP) experienced several significant wildfires last week, but connectivity in both Taylor Slough (TS) and Shark River Slough (SRS) remained relatively steady over the last month. Water depths remain in the 10th – 20th percentile for this time of year across the EPA impacting soil, flora, and fauna. (**Figures EV-5 and EV-6**). Recurring below average water depths in the central Everglades are illustrating the system level importance of maintaining water in the sloughs and low water refugia for wildlife and vegetation needs.

Taylor Slough and Florida Bay

Most stages decreased across Taylor Slough over the past week, with an average decrease of 0.02 feet for the week. Changes ranged from -0.09 feet at Taylor Slough Bridge (TSB) in the northern slough to +0.08 feet at P37 in the southern slough (**Figure EV-7 and Figure EV-8**). Taylor Slough water levels remain below the recent average (WY1993-2016) for this time of year by 5.7 inches compared to before the Florida Bay Initiative (starting in 2017), a decrease of 0.8 inches relative to last week. Stages at Craighead Pond (CP) and TSB are below the estimated historical average by 1.21 and 2.46 feet, respectively.

Average salinity in Florida Bay was 43.2, a decrease of 0.3 from last week. Salinity changes ranged from -2.9 at Joe Bay (JB) in the eastern nearshore region to +3.4 at Garfield Bight (GB) in the western nearshore region (**Figure EV-7**). Salinity is above the estimated historical average and above the WY2001-2016 Interquartile Range (IQR) 75th percentile in all regions. (**Figure EV-9**). Salinity in the eastern region is at the hypersalinity

threshold, while the central and western regions are above it. Bay-wide salinity is above its recent average (WY1993-2016) for this time of year by 13.5, a decrease of 0.1 from last week's comparison.

Salinity at the Taylor River (TR) station in the mangrove zone (tracked for the Florida Bay MFL) was 28.3, a decrease of 6.8 from last week (**Figure EV-10**). The 365-day moving sum of flow from the five major creeks (McCormick Creek, Taylor River, Mud Creek, Trout Creek, West Highway Creek) was unable to be assessed due to missing data.

Average rainfall across Taylor Slough and Florida Bay was 0.40 inches for the week, based on the 18 gauges used for this report. Rainfall ranged from 0.00 inches at four stations to 2.33 inches at P37 in the southern slough (**Figure EV-11**). Wind directions and speeds in Florida Bay ranged from 0.2 mph S to 17.0 mph W, both on August 18th (**Figure EV-11**).

The Taylor River, Mud Creek, and West Highway Creek flow stations are currently offline until further notice, so data from all five major creeks are unable to be assessed. Based on the available data from Trout and McCormick Creeks, average daily flow totaled 207 ac-feet, with net positive flows for the week. Total daily creek flow ranged from -132 ac-feet on August 23rd to 580 ac-feet on August 22nd (**Figure EV-12**). Average daily flow from Alligator Creek was -12 ac-feet, with net negative flows for the week (**Figure EV-12**).

Implications/considerations for water management

- Due to current drought conditions, slow or no recessions and more ascensions would help to protect the wetland ecology from damaging dry conditions during the wet season.
 - With continued drought conditions, conserving water within the WCAs, especially WCA-3A, will continue to be ecologically beneficial.
- Freshwater input into Taylor Slough and the C-111 basin could help moderate salinities and support recovery of estuarine conditions in Florida Bay.
- Conserving water in the WCAs while providing freshwater input to the sloughs of ENP will require careful consideration of a balance between the upstream and downstream ecological needs of the system. Individual regional recommendations can be found in **Table EV-2**.

Table EV-1. Previous week's rainfall and water depth changes in Everglades basins.

Everglades Region	Rainfall (Inches)	Stage Change (feet)
WCA-1	0.59	-0.12
WCA-2A	0.58	-0.05
WCA-2B	0.57	-0.04
WCA-3A	0.84	+0.02
WCA-3B	2.45	+0.12
ENP	0.75	+0.16




Figure EV-1. WCA-1 stage hydrographs and regulation schedule.

WCA 2A (23 August 2026)




Figure EV-2. WCA-2A stage hydrographs and regulation schedule.

WCA 3A COP (23 August 2026)




Figure EV-3. WCA-3A stage hydrographs (three-gauge average, 3-69W) and regulation schedule.

WCA-3A (Deer) Gauge 62 (23 August 2026)




Figure EV-4. WCA-3A stage hydrograph (Deer gauge; Site 62) and regulation schedule.




Figure EV-5. Everglades water depths from two months ago (left), one month ago (center) and present (right), based on SFWDAT.




Figure EV-6. Present water depths (August 23, 2026) compared to the day of year relative to average (percentile) over the previous 20 years.




Figure EV-7. Taylor Slough water depths and Florida Bay salinities with changes since a week ago.




Figure EV-8. Taylor Slough water depth time series for Taylor Slough Bridge (TSB; northern slough) and Craighead Pond (CP; southern slough).




Figure EV-9. Eastern (top panel), Central (middle panel) and Western (bottom panel) Florida Bay daily average salinities with WY2001-2016 interquartile (25-75 percentile) ranges (IQR) and estimated historical daily average salinities. The hypersalinity threshold indicates the level at which salinities start to become harmful to seagrass.




Figure EV-10. Daily average salinity at Taylor River (TR) tracked for the Florida Bay MFL criteria. The 365-day total creek flow MFL metric is not currently available due to missing creek flow data.




Figure EV-11. Daily average rain across Taylor Slough and Florida Bay, along with hourly average wind speed and direction (measured at Long Key) in Florida Bay over the past four weeks.




Figure EV-12. Top: daily average creek flow summed between the five major creeks with estimated historical daily flow over the past four weeks (**note:** data from Taylor River, Mud Creek and West Highway Creek are currently unavailable since May 28th, 2026). Bottom: Daily average Alligator Creek flow data.

Table EV-2. Weekly water depth changes and water management recommendations

SFWMDC Everglades Ecological Recommendations, August 25, 2026 (red is new)			
	Weekly change	Recommendation	Reasons
WCA-1	Stage decreased by 0.12 feet	An ascension of no faster than 0.18 feet per week	Conserve water, maintain within basin and downstream habitat and wildlife. Maintain maintenance access for vegetation management.
WCA-2A	Stage decreased by 0.05	An ascension of no faster than 0.18 feet per week	Conserve water, maintain within basin (north versus south) and downstream habitat and wildlife.
WCA-2B	Stage decreased by 0.04 feet	An ascension of no faster than 0.18 feet per week	Protect within basin and downstream habitat and wildlife.
WCA-3A NE	Stage increased by 0.19 feet	An ascension of no faster than 0.18 feet per week	Conserve water, maintain within basin and downstream habitat and wildlife. Provide suitable depths for aquatic prey and protect against peat soil loss during the dry season.
WCA-3A NW	Stage decreased by 0.11 feet	An ascension of no faster than 0.18 feet per week	
Central WCA-3A S	Stage decreased by 0.11 feet	An ascension of no faster than 0.18 feet per week	Conserve water, maintain within basin and downstream habitat and wildlife. Provide suitable depths for aquatic prey and protect against peat soil loss during the dry season.
Southern WCA-3A S	Stage increased by 0.09 feet		
WCA-3B	Stage increased by 0.12 feet	An ascension of no faster than 0.18 feet per week	Protect within basin and downstream habitat and wildlife.
ENP-SRS	Stage increased by 0.16 feet	Make discharges to ENP according to COP protocol, considering up/down stream ecological conditions	Protect within basin and upstream habitat and wildlife.
Taylor Slough	Stage changes ranged from -0.09 feet to +0.08 feet	Move water southward as possible	When available, provide freshwater to promote water movement.
FB- Salinity	Salinity changes ranged from -2.9 to +3.4	Move water southward as possible	When available, provide freshwater to promote water movement.