

# Conceptual Plan for Achieving Long-term Everglades Water Quality Goals

*Technical Oversight Committee*

*June 3, 2003*

*Gary Goforth, P.E., Ph.D.*



[sfwmd.gov](http://sfwmd.gov)

# Overview

- **Background**
  - Everglades Forever Act requirements
  - Considerable progress to date
- **Conceptual Plan**
  - >3 years in the making
  - Early strategies in *Consolidated Reports*
  - Future actions

# Common Abbrev.

- ATT - Advanced treatment technology
- BMP - Best Management Practices
- C-# or L-# refers to Canal or levee
- CERP - Comprehensive Everglades Restoration Plan
- EAA - Everglades Agricultural Area
- ECP - Everglades Construction Project
- EFA - 1994 Everglades Forever Act
- ESP - Everglades Stormwater Program
- PSTA - Periphyton-based STA
- PDT - Project Development Team
- S-# or G-# refers to Structure
- SAV - Submerged Aquatic Vegetation
- STA - Stormwater Treatment Area
- TP - Total Phosphorus

# ACHIEVING EVERGLADES WATER QUALITY

## Mandated time frames

Implement Best Management Practices



Phosphorus rulemaking began



Adopt phosphorus criterion



Compliance with water quality standards



12/99      12/00      12/01      12/02      12/03      12/04      12/05      12/06

Construct STAs



Evaluate basin-specific alternative combinations of BMPs, STAs and ATTs; begin design



Long-term plans & permit application



Design & construct long-term solutions



Research STA optimization and advanced treatment technologies



**ECP Basins:**



**STA-1E**


**STA-1W**

**STA-2**

**STA-3/4**

**STA-5**

**STA-6**



**ESP Basins:**



**ACME Basin  
"B"**

**North Springs  
Improvement  
District**

**North New  
River Canal**

**C-11 West**

**L-28**

**Feeder Canal**

**C-111**

STA	Effective Areas (Acres)	EFA* Completion Date
STA-1 East	5,350	7/1/2002
STA-1 West	6,670	1/1/1999
STA-2	6,430	2/1/1999
STA 3 / 4	16,480	10/1/2003
STA-5	4,118	1/1/1999
STA-6, Section 1	870	10/1/1997
STA-6, Section 2	1,410	N/A

\*Everglades Forever Act

**C-111**

# Progress to Date

- **Implemented EAA BMPs**
  - Performing better than expected
  - Averaging >50% load reduction
- **Stormwater Treatment Areas**
  - Four are operational
  - STA-1E and STA-3/4 under construction
  - Average performance better than expected
- **Additional measures will be needed to meet water quality goals**

# Basin-Specific Feasibility Studies

- Evaluated combinations of BMPs, regional treatment works, and integration with CERP
  - Technical, economic and other factors
- Scientific uncertainties remain, however:
  - Models suggest possibility to achieve goals for 80-90% of discharges by Dec. 2006
    - STAs Enhancements
  - Potential for substantial economic benefits by integrating with CERP projects
    - Over \$750 million in capital costs, if projects developed independent of CERP

# Conceptual Plan

- A Conceptual Plan to achieve compliance with water quality standards - based on years of peer-reviewed investigations and engineering studies
- Developed by technical experts and consultants
  - Same core group that developed the 1994 Conceptual Design
- Will serve as basis for District's long-term permit applications due 12/31/2003

# Plan Principles

1. Implement scientifically defensible improvements by December 31, 2006
2. Continue technical investigations to evaluate further improvements
3. Implement additional steps as soon as the need and feasibility are confirmed
4. Integrate with other regional efforts, CERP in particular
5. Accelerate the recovery of impacted areas within the Everglades

# Plan Components

- **Everglades Construction Project**
  - Source controls (BMPs)
  - STA optimization
  - Implementation of additional measures after 2006
- **ESP Basins**
  - Source controls
  - Integration with CERP
  - Implementation of additional measures after 2006
- **Continue science-based investigations**
- **Accelerate recovery of impacted areas**

# Everglades Construction Project Basins

- Enhanced source controls in EAA, C-139 and C-51W basins
- STA Enhancements by Dec. 2006
  - Additional compartmentalization
  - Vegetation management
  - Operational refinements
- STA operation, maintenance & monitoring
  - Structure, levee, canal, vegetation
  - Flow and water quality monitoring

# Everglades Stormwater Program Basins

## ■ Source Controls by Dec. 2006

- Ordinances, landowner agreements & capital projects
- Hot spot identification and remediation
- Expanded water quality outreach

## ■ Integrate with CERP

### ■ Most promising alternatives:

- Acme Basin B treatment in STA-1E
  - Diversion of C-11 West (S-9), NSID and NNRC
  - Accelerate modification of L-28 Interceptor Canal
  - Accelerate STAs on Tribal lands
- *CERP process will make final decisions - no change in cost-share relationship*


## **Continue Scientific Investigations**

- Referred to as Process Development and Engineering (PDE)
- Improve performance of urban and agricultural BMPs
- Enhance performance of STAs
- Improve forecasting tools and data sets


# Adaptive Implementation

- \$36 million allocated beginning in 2007
- Objective is to further reduce TP in discharges
- Includes both ECP and ESP basins
- Potential enhancements include:
  - Integration with CERP projects
  - Conversion of additional lands to SAV, PSTA or other vegetative communities
  - Additional structural and operational modifications within existing STAs
  - Implement enhanced BMPs

### Estimated Annual Phosphorus Loads to the Everglades



### Estimated Annual Phosphorus Concentrations




# Recovery of Impacted Areas

- **Before Dec. 2006**
  - Investigate measures to accelerate recovery
  - Improve forecasting models
- **After Dec. 2006**
  - Hydropattern restoration works
    - Distribution, volume and timing
    - Integrate with CERP hydropattern restoration
  - Active management within the water conservation areas

# Preliminary Costs Through 2016

- **Everglades Construction Project**
  - STA optimization: \$52.4 million
  - Existing O&M: \$189.5 million
  - Performance support: \$91.5 million
- **Everglades Stormwater Program: \$1.4 million**
  - Other local, state and federal funds
- **Science-based investigations: \$32 million**
- **Adaptive implementation: \$36 million**
- **Recovery of impacted areas: \$47.7 million**

### Conceptual Plan Annual Cost Estimates \$450 million through FY 2016



May be additional costs for further integrating with CERP projects

# Plan Summary

- Reduce phosphorus levels to Everglades
- Accelerate recovery of impacted areas
- Integrate with CERP projects
- Provide basis for SFWMD long-term permit applications

# Future Steps

- Plan has been under review for >60 days
- Public - solicited review from 100s of individuals
- Federal agencies
  - Corps of Engineers - STA-1E & CERP process
  - Dept. of Interior, U.S.E.P.A.
- District: \$ estimates, schedules, constraints
- Legislative and ERC actions
- Anticipate presenting revised plan to Governing Board in October/November as part of long-term permit application