SOUTH FLORIDA WATER MANAGEMENT DISTRICT

System-Wide Modeling for EAA Storage Reservoirs


For

EAA Storage Reservoirs Phase 1

By

Ken C. Tarboton, Ph.D., P.E. And Lehar Brion, Ph.D., P.E.

July 25, 2002





Outline


What modeling was done in Restudy

- What modeling has been done since Restudy
 - Scenarios
 - LEC
 - ECP & Basin Specific Feasibility Study
- What modeling is coming up
 - Initial CERP update
 - SFWMM refinements

EAA Reservoirs in D13R

"The initial design for the reservoirs assumed 60,000 acres, divided into three equally-sized compartments (1, 2A, 2B), with the water level fluctuating up to six feet above grade in each compartment. The final size, depth, and configuration of this facility will be determined through more detailed planning and design."

EAA Reservoirs in D13R



Total Storage (360,000 ac-ft) Equivalent to 0.8 ft on LOK


Compartment #1 (120,000 ac-ft)

 used to meet Everglades Agricultural Area irrigation demands

Compartments #2&3 (each 120,000 ac-ft)

 used to meet environmental demands as a priority

Figure 1. Trigger Lines for North of Lake Okeechobee Storage and Lake Okeechobee Aquifer Storage and Recovery (ASR)



or if stage is above Pulse Release Z one (level 1) line.

System-Wide Modeling Since Restudy

EAA-Related Model Input Requirements

- Scenarios based on Alt. D13R
- LECECP & BSFS

EAA Reservoir Related Model Input Requirements


Reservoir Configuration number of compartments footprint storage capacity (min/max depth) Operational Criteria sources & destinations of flows pump/structure capacities

operating rules (e.g., trigger levels, priorities)

EAA Reservoir Scenarios

- Based on CERP (D13R)
- Double size of Reservoir 2 (SGT4020)
- Remove Reservoir 3 (SGT1x20)
- Remove Reservoirs 2 & 3 (EAARS)
- Remove all EAA Reservoirs (NEAARS)

Described in Central and Southern Florida Project, Comprehensive Review Study, 1999, Appendix B-68,69,104-141










EAA Reservoir Configuration in LECRWSP

Compartment 1 increased to 30,000 acres #1 Compartment 2A remains 20,000 acres #2 Compartment 2B decreased to 10,000 acres #3 Interbasin transfers to better utilize compartment 1



HYDROLOGIC SYSTEMS MODELING

efund-gov

ECP & BSFS Modeling

Used in support of Everglades Construction **Project and Basin-Specific Feasibility Study** Updated Alt. D13R to include latest Talisman footprint using a more recent version of SFWMM Included phases 1 & 2 of EAA Reservoir Project (as in Alt. D13R)

What Modeling is Coming Up

Initial CERP update (ICU) Refinements to SFWMM



Initial CERP Update

Using additional data

- Upgrading the system-wide simulation models
- Re-simulating the Comprehensive Plan

Additional Data

Extended Climatic record by 5 additional years to include data through December 2000.

Updated topography

Latest USGS topo in ENP and WCA-3

Updated land cover

Iatest satellite images (1995) and areal photographs (2000)

Updated population projections and associated water demands

System-Wide Simulation Models

SFWMM NSM ELM LOKWQM ATLSS RSM



Refinements to SFWMM (SFWMM v 5.x)

- Ability to use 36-year record
 - Modified performance measures and incorporated new performance measures

Code modifications

- small reservoirs
- ASR recovery across basins
- WSE schedule for LOK
- Position analysis mode

Refinements to SFWMM continued (SFWMM v 5.x)

- Forward pumping from LOK
- Ability for water supply backpumping of EAA runoff
- Day specific deliveries to meet supplemental EAA and LEC demands
- Structure specific operations for selected structures

Design Suggestions

- CERP (Alt D13R) is a good starting point; more detailed analysis is needed
- Look for opportunities to optimize local design for system-wide benefits.
- Consider lessons learned from other modeling (Alt. D13R scenarios, ECP, LEC)
- Ensure optimization of components that work with EAA Reservoirs, through RECOVER
- Pay close attention to ICU and ASR contingency modeling

Resources

C&SF Comprehensive Review Study, Hydrologic Performance Measures web Page

http://www.sfwmd.gov/org/pld/restudy/hpm/

- C&SF Comprehensive Review Study, Hydrology and Hydraulics Modeling, Appendix B.
- Lower East Coast Regional Water Supply Plan, SFWMD, May 2000.
- Scenario Simulations for Reservoirs in the EAA. Memorandum from R. Santee & L. Cadavid to C. Neidrauer, September 4, 1998

Resources

- 2010 Case Study with EAA Reservoir Storage Volume Doubled, Novoa and Tarboton, 2001, http://www.sfwmd.gov/org/pld/hsm/pubs/evals/eaarsx2_final_100101.pdf
- Modeling of EAA Storage Reservoirs in SFWMM D13R Restudy Run. Memorandum from Raul Novoa to Victor Powell, July 9, 2001

ECP Base Simulation and 2050 with Project
Simulation Using the South Florida Water
Management Model. Memorandum from L. Brion and A.
Ali to G. Goforth & T. Piccone, April 15, 2002