## **DECOMP Physical Model (DPM)** Implementing Adaptive Management in the Everglades

Matt Morrison, Everglades Policy & Coordination Fred Sklar, Ph.D., Everglades Systems Assessment

Governing Board Meeting March 9, 2017

## **Central Everglades Planning Project (CEPP)**

- Authorized in Water Resources Development Act in Dec 2016
- Projected Cost \$1.98 Billion



**Historic Everglades** 



**C&SF** Project



## **CEPP Distribution and Conveyance**



### **Decompartmentalization Uncertainties**

- Extent of canal backfilling and levee removal required to maintain sheetflow
- Surface water flow velocity required for creating and maintaining ridge and slough habitat and landscape
- Influence of new project features on water quality

### **Decomp Physical Model**

- Provides opportunities to address project uncertainties
- Includes adaptive management strategies to help inform project implementation and future project operations

## Restoring Ecological Function Means Restoring the Ridge-Slough-Tree Island Pattern



During the wet season, flows distribute nutrients, food and floc (Everglades "topsoil")

During the dry season, wading birds feed in the sloughs and nest in the tree islands

### Deep Within the Everglades, Away From Any Influence of High Nutrient Inflows, Sloughs are Disappearing



Pre-drainage ridge & slough landscape pattern (50% slough)



Impacted ridge & slough landscape pattern (30% slough)



Ridge & slough pattern is completely gone and replaced by willow trees, cattails and dense sawgrass.



## Restoring Ecological Function Means Restoring the Ridge-Slough-Tree Island Pattern





## What is the Decomp Physical Model (DPM)?



- A landscape manipulation (levee removal, canal fill and inflow culverts) designed to provide critical information of the hydrologic and ecological targets for Everglades restoration
- A pilot study that provides "ecological lift" to a drained system
- It is the second largest <u>Adaptive</u> <u>Management</u> project in the USA

## **Specific Questions to be Answered by DPM**

<u>Uncertainty 1</u>: Restoration: What is the ecological function of sheetflow and what are the hydrologic needs (i.e., flow fields, depths, duration) of the ridge and slough landscape?

<u>Uncertainty 2:</u> Hydrology: Do canals need to be completely backfilled in order to achieve hydrologic restoration?

<u>Uncertainty 3</u>: Sediment: What is the role of floc and sediment movement for restoring and sustaining a stable ridge and slough landscape, and how do canals, levees, and levee modifications affect this movement?



## **Aerial Overview of DPM Project Location**



## **Aerial Overview of DPM Project Location**







## U.S. Army Corps of Engineers was Responsible for Project Construction



S-152 Discharge Structure includes 10 – 60" gated culverts

## L67C canal backfill & levee removal



High Velocities (3-4 cm/sec) in the Sloughs at 1300 hrs, But Not in the Direction Expected

### Southeast flow was expected

Easterly flow was the result



## DPM Hydrologic Flow Fields: Using Velocimeters and Water Tracers



- Flows did not follow the ecologically preferred pattern
- Velocities across the pocket ranged from 2 -10 cm/sec
- High flows were detected in the gap in the L-67C

## Why do we care about velocity?

Because high flows can redistribute floc from sloughs to ridges





## **Tracking Floc Movement and Deposition**

## Slough Center

S-152

## Ridge-Edge

### Slough-Edge

### South Florida water Management district Sustained Flows Resulted in Increased Slough Velocities & Floc Transport



Data from J. W. Harvey, J. Choi, M. Dickman

## **Floc Response to Flow**





## **Canal Restoration Uncertainties**

- Do canals reduce natural sediment transport?
- Do canals mobilize high-Phosphorus canal sediments?
- Does backfilling effectively bury canal sediments?
- Does backfilling alter fish habitat quality?



### **Phosphorus Sources: Marsh vs Canal**



sfwmd.gov

Data from L. Larsen (UCB), J. Harvey (USGS), C. Saunders and C. Coronado-Molina (SFWMD). \* L-28 data from Merkel & Hickey-Vargas 2000





## **Backfilling and Fish Habitat Quality**



Backfill treatments created more high quality fish habitat

Revegetation of backfill areas continues to evolve and will be monitored as part of DPM Phase 2

### CPEU = Catch per Unit Effort



## **Key Decomp Physical Model Results\***

- Surface water flows are not following the historic ridge and slough flow-paths.
- Sustained flows and high velocities are needed to rebuild the ridge and slough topography.
- Sustained flows increase slough velocities and sediment transport.
- Canals with limestone fill can prevent canals from acting as sediment traps.
- Backfilling canals can improve habitat quality for large fish.
- Canals with limestone fill can cap the legacy phosphorus and reduce sediment phosphorus transport downstream.

<sup>\*</sup> Findings are preliminary as canal treatments continue to recover from construction disturbance and re-vegetation

## **Extending Operation of the DPM**





- In February 2016, DEP Emergency Order authorized continued use of S-152 to aid in relieving high water conditions in WCA3A
- Extended operation of the DPM over the next three years will increase flows into WCA-3B and reduce uncertainties associated with the Blue Shanty Flow-way
- Contract is item #20 on the March Governing Board agenda

# DPM Phase 2: Focus on food-webs, slough modifications & WCA-3B

### Can we "jump start" flow restoration?



# DPM Phase 2: Focus on food-webs, slough modifications & WCA-3B

## We will test the "jump start" concept by reconnecting old sloughs in the "pocket"



## **Questions?**



## Agenda Item # 20

## **Resolution No. 2017 - 0304**

A Resolution of the Governing Board of the South Florida Water Management District to enter into a four-year contract with Florida Atlantic University to conduct field monitoring for assessing biological responses to sheetflow and canal filling, as part of the Decomp Physical Model project in an amount not to exceed \$550,000 of which \$125,000 is budgeted in Fiscal Year 2016 - 2017 from Alligator Alley Toll funds and the remainder is subject to Governing Board approval of future year budgets. (Contract No. 4600003624)